

**EXPLORATION PERMITS - MINERALS**

**NT-1-MEP**

and

**NT-2-MEP**

**Minerals (Submerged Lands) Act, 1981**

**Report on Activities for Period**

**Completing 19 January 1993**

**Bonaparte Gulf Area  
of the Kimberley Region  
Western Australia**

Prepared by  
Peter J Jones  
General Manager  
Cambridge Gulf Exploration NL  
18 High Street  
PO Box 797  
Fremantle WA 6100  
Telephone: (09) 430 6100  
Facsimile: (09) 430 5928

**23 December 1992**

**CR 93 / 188A**

## **CONTENTS**

- 1. Introduction**
- 2. Progress to Date**
- 3. Proposed Work Programme**
  - 3.1 Seismic Survey**
  - 3.2 Geotechnical Model**
  - 3.3 Bulk Sampling**
  - 3.4 Evaluation of Bulk Sample**
- 4. Expenditure for Year 2**
- 5. Expenditure to 19 January 1993**
- 6. Request for Variation**

### **Appendix I**

**Victoria River  
Palaeo Channel Survey  
by Associated Surveys International Pty Ltd  
30 April 1992**

### **Appendix II**

**Form 5  
Report on Operations on Mining Tenement**

## **1      Introduction**

Cambridge Gulf Exploration NL (Cambridge Gulf) applied on 7 August 1990 for exploration permits NT-1-MEP and NT-2-MEP in accordance with the Minerals (Submerged Lands) Act, 1981.

These exploration permits were granted on 19 January 1992.

Currently Cambridge Gulf holds a further two exploration leases in the Joseph Bonaparte Gulf under the Minerals (Submerged Lands) Act, 1981.

These leases are WA-1 MEP and WA-4-MEP under the control of the Western Australian Department of Mines and Energy.

A significant amount of work and expenditure has been carried out on all these leases with a specific focus on one lease,WA-1-MEP. The intent is to prove conclusively the scientific and geological evidence gathered on each of these leases and to develop a method of bulk sampling that realistically indicates the quality , quantity and reserve of these unique mineral deposits. To do this it is intended to carry out the first bulk sample on WA-1-MEP then apply the techniques develop to exploration permits NT-1-MEP and NT-2-MEP.

This report is prepared to comply with the requirements of Schedule 2 - "Conditions" of the exploration permit.

## **2      Progress to Date**

Cambridge Gulf has carried out two major on site investigation programmes and has undertaken a number of desk top studies to model fluvial and marine occurrences and reviewed papers on the formation of the Joseph Bonaparte Gulf and the influence of contributing rivers.

Information on the occurrence of diamond in the tributaries to the Joseph Bonaparte Gulf has brought new factors into the scientific model.

In 1989, Cambridge Gulf undertook an investigation programme in the Joseph Bonaparte Gulf that identified submerged palaeo rivers were evident in near proximity to current day river sequences.

These palaeo rivers contain deposition of gravels and sands in layered formation from the seabed down to basement rock.

Further evidence from the high resolution shallow seismic surveys and attempts to take samples from seabed suggests that the palaeo rivers are the only areas that contain these terrestrial sediments.

Resulting from the 1989 survey a programme for further exploration of palaeo rivers in the Joseph Bonaparte Gulf was set down.

The programme included a detailed seismic survey in exploration lease area WA-1-MEP over the palaeo Ord River to produce a geotechnical model and to target sites for bulk sampling.

This seismic survey work was undertaken in August 1991 and the geotechnical model completed during 1992.

The programme also required that a reconnaissance survey be undertaken in lease areas NT-1-MEP and NT-2-MEP.

In conjunction with the work on WA-1-MEP approximately 190 line kilometres of high resolution shallow seismic profiling data was gathered over NT-1-MEP and NT-2-MEP and a report prepared (see appendix 1).

The reconnaissance seismic profiling indicates that palaeo channel exist in both of the Northern Territory lease areas.

Concurrently with the site field work a special purpose bulk sampling vessel has been evaluated and identified as being suitable for our operation. Negotiations are nearing completion for securing its services with delivery to Australia in the first quarter of 1993.

### **3      Proposed Work Programme for Year 2**

The work proposed within the exploration permit NT-1-MEP is in four distinct parts.

Work proposed for year two for exploration permit NT-2-MEP is identical to that for NT-1-MEP as with the costs.

#### **3.1    Seismic Survey**

A closely spaced high resolution shallow seismic survey will be undertaken over submerged palaeo river channels now defined in the lease area.

This survey will be controlled to high accuracy using a Syledis or DGPS positioning equipment.

Approximately 500 line kilometres of seismic survey will be run in this lease area. The cost of this work is estimated at \$150,000.00.

### **3.2 Geotechnical Model**

The charts from the seismic survey will be interpreted in respect sea bed, interbedding gravels and sands and bedrock and modelled on our computer together with the positioning data to produce a geotechnical model of the stratigraphy of the palaeo channel sediments.

From this model and its data base, bulk sampling sites will be targeted.

The aim of the bulk sampling survey will be to assess the nature and concentration of valuable minerals, in particular diamonds, which may be present within gravel units. Finer grained heavy mineral-type accumulations may also be present.

The criteria for selection of the bulk sample sites would be as follows:

- Sampling sites to be located over seismic traverses to provide direct comparison with the geotechnical model data base.
- Sampling to investigate different geological unit combinations identified in the survey area.
- Sampling to be representative and extend to bedrock.
- Sampling to take the optimum situation of thin overburden, thick gravel concentration, presence of more than one gravel type and presence of favourable channel structures.

The cost of this work is estimated at \$35,000.00.

### **3.3 Bulk Sampling**

A special bulk sampling vessel with an on board heavy media separation plant will be employed to remove gravels and sands down to bedrock by reverse circulation.

The gravels and sands are processed by screening to size without crushing and concentrated heavy minerals of SG greater than 2.9 separated using forro silicon as the concentrating media.

The concentrate is retained for further processing onshore though a diamond recovery Sortex machine.

The ferro silicon is recovered in the process and all material with SG less than 2.9 returned to the seabed at the sampling site.

During the bulk sampling operation material samples will be taken continuously from the HMS plant circuit to evaluate if other valuable minerals are present.

The duration of sampling will be 20 days.

The cost of the bulk sampling operation will be \$750,000.00.

### **3.4 Evaluation of Bulk Sample**

The data collected during the bulk sampling operation will be reviewed against the geotechnical model.

From this information it will be decided if further sampling is required to define the size of the reserve or if there are anomalies that require further investigation that may increase the value of the reserve.

The positive actions that may take place after this stage are:

- Carry out further bulk sampling
- Preparation of a bankable document to fund the capital expansion required for full scale mining.

Anticipated expenditure \$60,000.00.

## **4 Expenditure for Year 2**

Summary of expenditure for the next 12 months.

	NT-1-MEP	NT-2-MEP
Seismic Survey	\$150,000.00	\$150,000.00
Geotechnical Model	\$35,000.00	\$35,000.00
Bulk Sampling	\$750,000.00	\$750,000.00
Evaluation of Bulk Sample	\$60,000.00	\$60,000.00

## **5      Expenditure to 19 January 1993**

A total of \$362,000.00 was expended on exploration permit NT-1-MEP and the same amount for NT-2-MEP up to 19 January 1993.

This falls short of the expenditure required of \$530,000.00 for each of the permits for the first twelve months term.

The shortfall has been caused by the delay in the commencement of bulk sampling due mainly to the sourcing of correct equipment to undertake this operation. The equipment is currently undergoing sea trials and will initially be used on the Western Australian lease area for reasons as described earlier.

When the equipment arrives during the first quarter of 1993 for WA-1-MEP the seismic vessel will be mobilised to NT-1-MEP and commence the work needed to develop the geotechnical model. On completion it will proceed immediately to NT-2-MEP.

The bulk sampling programme will commence on NT-1-MEP during the last quarter of 1993 and continue onto NT-2-MEP. The work will complete at the end of 1993.

## **6      Request for Variation for Exploration Permits NT-1-MEP and NT-2-MEP**

It is requested that under section 67 of the Act that condition number 1 of both exploration permits be varied so that the minimum expenditure to be expended by January 1993 be \$362,000.00.

The expenditure requirement for the first two years of \$950,000.00 for each of the permits will be complied with.

## REPORT ON OPERATIONS ON MINING TENEMENT

(To be completed in accordance with the instructions on the reverse hereof)

Tick box  
applicable

Annual       Final       Surrender, Report for the

Period from                  To 19 January 1993

### Details of Mining Tenement:

Type Nt-1-MEP                  Number

Brief  
summary of  
operations  
for each if  
applicable

### SUMMARY OF OPERATIONS AND EXPENDITURE:

**General Prospecting:** (Specify: Costeaning No.; Metal detecting man days;  
Sampling No., etc)

Cost \$

**Remote Sensing & Airborne Surveys:** (Specify: Photography; Surveys  
Line km; etc)

Sub bottom profiling surveys - 10% of 650  
kilometre survey and 90 kilometre of survey      Cost \$114,000.00  
August 1991

**Ground Surveys:** (Specify: Type; Line km; etc)

Cost \$

**Drilling:** (Specify: Type; No. of holes; Metres; etc)

Design, research and locating suitable equipment  
to undertake bulk sampling operation

Cost \$43,000.00

**Mining or Development:** (Specify: Development; Tonnes mined; etc)

Cost \$

**Overheads:** (Specify: Report preparation; Office studies; etc)  
Consultants reports

Cost \$97,000.00

Planning of Geophysical programme  
Planning of bulk sample operation

Specialist Consultants

Funding Expenses

Other Costs: (Specify: Labour own/hired; Plant hire; Transportation,  
Construction, Fuel; etc).

Overseas travel and accommodation to review bulk  
sampling techniques and capital raising      Cost \$108,000.00  
- site visits to Kimberley area  
- Computer systems

TOTAL EXPENDITURE \$362,000.00

Note: A copy of this page of the report may be obtained by any person on the payment of the prescribed fee—  
Regulation 96 (2)

55239/7/87—20M—AS/1192

## REPORT ON OPERATIONS ON MINING TENEMENT

(To be completed in accordance with the instructions on the reverse hereof)

Tick box  
applicable

Annual       Final       Surrender, Report for the

Period from                  To 19 January 1993

### Details of Mining Tenement:

Type NT-2-MEP                  Number

Brief  
summary of  
operations  
for each if  
applicable

### SUMMARY OF OPERATIONS AND EXPENDITURE:

**General Prospecting:** (Specify: Costeaning No.; Metal detecting man days;  
Sampling No., etc)

Cost \$

**Remote Sensing & Airborne Surveys:** (Specify: Photography; Surveys  
Line km; etc)

Sub bottom profiling surveys - 10% of 650  
kilometre survey and 90 kilometre of survey      Cost \$ 114,000.00  
August 1991

**Ground Surveys:** (Specify: Type; Line km; etc)

Cost \$

**Drilling:** (Specify: Type; No. of holes; Metres; etc)

Design, research and locating suitable equipment  
to undertake bulk sampling operation      Cost \$ 43,000.00

**Mining or Development:** (Specify: Development; Tonnes mined; etc)

Cost \$

**Overheads:** (Specify: Report preparation; Office studies; etc)

Consultants reports

Planning of Geophysical programme

Planning of bulk sample operation

Cost \$ 97,000.00

Specialist Consultants

Funding Expenses

Other Costs: (Specify: Labour own/hired; Plant hire; Transportation,  
Construction, Fuel; etc).

Overseas travel and accommodation to review bulk  
sampling techniques and capital raising      Cost \$ 108,000.00  
- site visits to Kimberley area  
- Computer systems

TOTAL EXPENDITURE \$ 362,000.00

Note: A copy of this page of the report may be obtained by any person on the payment of the prescribed fee—  
Regulation 96 (2)  
55239/7/87—20M—AS/1192

Ref:4660SD

**BRIEF REPORT  
VICTORIA RIVER  
PALAEO-CHANNEL SURVEY**

CR 93 / 1888B

**FOR:** **CAMBRIDGE GULF EXPLORATION NL**  
**18 HIGH STREET**  
**FREMANTLE. W.A.**

**BY:** **ASSOCIATED SURVEYS INTERNATIONAL PTY LTD**  
**18 PROWSE STREET**  
**WEST PERTH. W.A.**

## PALAEO-CHANNEL SURVEY

Approximately 180 km of reconnaissance echo sounder and high resolution shallow seismic profiling data were acquired during 28th to 30th August, 1991, offshore from the Victoria River in the southern Joseph Bonaparte Gulf of the Northern Territory and Western Australia.

The accompanying Figure 1 shows the layout of the three survey lines relative to shoreline features identified from the Admiralty Chart AUS 316.

Survey and other operations are detailed in the separate report titled "Palaeo-Channel Survey in WA-1-MEP, Joseph Bonaparte Gulf, Western Australia". This report also presents a background synthesis of regional geology and interpretations of past depositional environments in the southern Joseph Bonaparte Gulf.

The accompanying map Plan Number 8428-55, shows the survey fix trackplot at 1:100,000 scale and interpretations of the seismic data.

Note that because of the line spacings of tens of kilometres, the continuity of features is largely conjectural from line to line, however the map does show the possible style of channel features that would be better delineated by a closer survey grid.

The map shows present channels and older, infilled relict channels and estimates of depths below sea level to the deepest parts of each channel.

These depths are determined by converting the seismic record time scale using assumed seismic velocities for sea water and sediments.

Echo sounder data are not used to obtain more accurate bathymetry, because there is no tidal data sufficiently reliable for accurate reductions.

The map shows two presently active branching channel systems up to 4km wide and varying in depth between near 35m inshore to almost 45m offshore, and conjectured as extending northwards from the present day river mouth.


Two minor channels are also shown further west on one survey line.

SCALE 1 : 500000

VICTORIA RIVER PALAEO CHANNEL SURVEY  
LOCALITY MAP ( REFER AUS. 316 )

FIGURE 1

JOSEPH      BONAPARTE  
GULF



This channel system supersedes an infilled channel system with possibly three branching channels up to 5 or more kilometres wide, trending west of north and varying in depth between approximately 40 and almost 60 metres, with one channel more than 70 m deep.

Several minor infilled channels in this range of depths are shown on one survey line to the west.

Between this channel system and the overlying present channels is a zone of seismic masking attributed to gas being generated in peat beds. This is interpreted as an ancient mangrove swamp, and is taken as firm evidence for lower sea levels in the past, and supports the claims made in the WA-1-MEP report for the presence of fluvial and deltaic deposition in the southern Joseph Bonaparte Gulf, pre-dating the present estuarine and marine environment.

A third older channel system is also indicated on the map, also trending west of north from the present river mouth. This appears to comprise a major central channel more than 10 km wide and approximately 70 m or more deep, and a lesser eastern channel, 5 km wide and 80 m deep.

The offshore extent of the major channel is obscured on the seismic records by the shallow water seabed multiple.

This multiple also obscures deeper seismic features which may be indicative of even older broad channel features.

A closer survey grid may assist in determining the presence of such possible older features, however useful delineation may only be possible by seismic techniques such as multi channel acquisition which will reduce the multiple problem.

In conclusion, this survey has shown the presence of significant palaeo-channel systems offshore from the Victoria River mouth, which are very likely to have developed at periods of lower sea level within fluvial and deltaic depositional regimes.

Further appraisal of this area will require a confident assessment that these palaeo-channels have drained from areas with diamondiferous potential, and if this criteria is satisfied, then a closer spaced seismic survey will be required for more confident delineation of the palaeo-channel geometry and identification of coarse fluvial deposits.



## ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT	CGE	JOB NO.	HY8428 6	DATE	24/8/91
LOCATION	WYNDHAM	VESSEL	HERMAD ACHIEVER		

FROM	TO	SUMMARY OF OPERATIONS
0000	2400	ALONGSIDE WHARF IN WYNDHAM. JOINED BY T. GANS, J GRANDORGE CGE.
1100		A TERRILL ARRIVES FROM KUNUNURRA
1400		A LANE DEPARTS FOR KUNUNURRA/PEARTH
1600		ELCS EQUIPMENT ARRIVES VIA CHARTER AIRCRAFT
1700		ELCS EQUIPMENT TEMPORARILY INSTALLED AND TESTED OK.
1900		ALL EQUIPMENT INSTALLED READY FOR DEPARTURE
2000		WORK COMPLETE FOR DAY
2100		PHONE REPORT TO TED GANAHAM.

EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
MOBILIZATION				LAURIE SKINNER	SURVEYOR
NO EQUIPMENT				LAURIE ETHERIDGE	TECIT
ON CHARGE.				ADRIAN SAROLEA	DATA. PROC
				ANDY GANE	GEO
				ALAN TERRIC	"
CONSUMABLES					
VEHICLE					
ACCOMMODATION					

## AUTHORISED CONTRACT CHANGES/COMMENTS

PARTY CHIEF'S SIGNATURE	CLIENT REPRESENTATIVES SIGNATURE	DOR
<i>Allan Terrell</i>	<i>J.M. Grandorge Jig.</i>	2680



ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT	C.G.E.	JOB NO.	8428	DATE	25/8/91
LOCATION	CAT BRIDGE GULF	VESSEL	MERMAID ACHIEVER		

FROM	TO	SUMMARY OF OPERATIONS			
0000	0600	ALONGSIDE WYNDHAM WHARF			
	0600	BAR CHECK - AT VS 1534 TD TO 2.22.			
		CAST OFF, DEPLOY S.S.S.			
0620	1005	E/S + SSS. SURVEY DOWN WYNDHAM CHANNEL.			
1005	1345	PULL SSS FISH + E/S TRANSDUCER. PROCEEDED AT SPEED FOR LOCIN.			
	1345	TS PROBE AND DEPLOY BOOMER, START TUNING VS 1530			
1446	1615	SOL 395000 10.11 km (10.11 km)			
1620	1719	UNCONTROLLED LINE ON TOP OF BANK. NO SATELLITES			
1719	2125	INSUFFICIENT SV'S			
2125	2249	LINE 377000 8.40 km (18.51)			
2302	2350	LINE 376000 5.45 (23.96)			
	2350	LINE 376000 ABORTED BECAUSE RND DUE TO EPIHEMIS			

## CHANGES

EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
PC NAV SYSTEM	1	EG + G HYDRO	2	Laurie Skinner	SURVEYOR
DGPS SYSTEM	1	EG+G 23/232A	2	ACLAN TERRILL	GEOPHYSICIST
PC MAP SYSTEM	1	DEPTH-1	1	Laurie Etheridge	TECH
DESO 20 SONAR	2	OYO PLOTTER	1	ADRIAN STOKES	DATA PROC
ASH TECH RECEIVER	2				
PACRATT MODEM	2				
SSB HF RADIO	2				
T.S. PROBE	1				
EG + G ANCHOR	1				
CONSUMABLES		1x5Y QUEST DISK, 1x E/S ROLL			
VEHICLE					
ACCOMMODATION					

AUTHORISED CONTRACT CHANGES/COMMENTS

PARTY CHIEF'S SIGNATURE  
CLIENT REPRESENTATIVES SIGNATURE  
DOR  
2681



## ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
ASHTECH RCVRS	2	OYO PLOTTER	1	ALAN TERRILL	GEO / PC
SSB RADIOS	2	ANALOGUE BOMER	1	Laurie Skinner	SLRV.
DGPS SYSTEM	2	(SPARE SYSTEM)		Laurie Etheridge	TECH
PCNAV SYSTEM	2			ADRIAN SAROLEA	PROC.
PLOTTER 'AO'	1				
DESO 20 E/S	2				
UNI BOOM	1				
231/232A	2				
DELPH I	1				
CONSUMABLES		1 x SYQUEST DISK, 1 x OYOROLL, 1 x E/S ROLL			
VEHICLE					
ACCOMMODATION					

---

**AUTHORISED CONTRACT CHANGES/COMMENTS**

---

PARTY CHIEF'S SIGNATURE

**CLIENT REPRESENTATIVES SIGNATURE**

DOR  
2682



ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT	C G E	JOB NO.	8428	DATE	27/8/91
LOCATION	BONAPARTE GULF	VESSEL	MIRMAID ACHIEVER		
FROM	TO	SUMMARY OF OPERATIONS			
0004	0249	LINE 400,000	23.69 km (74.57 km)		
0249	1115	WINDOW CLOSED, REST PERIOD			
	1115	TS PROBE, UP ANCHOR PROCEEDED TO SOC VS 1530			
1211	1329	LINE 398000	9.76 (84.33 km)		
1410	1508	LINE 403000	8.48 (92.81 km)		
1520	1632	LINE 404000	8.18 (100.89 km)		
1632	2030	DTS WINDOW OFF HEADING TO NEW LINE			
2030		LINE 380,000, PDOP 2 + 5 SV'S AT SOC, ZDRMS 2-3 m			
2034	2216	NODGPS LINK FROM 2030-35, STAND ALONE FROM 2045			
2251	2342	DGPS LINK RE-ESTABLISHED. HEADING FOR NEW LINE			
2342	2359	LINE TIELINE 1# - STOP TO RESET SOFTWARE			
		3.13 km (114.10)	9.98 (110.47)		
EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
ASHTECH RCVR	2	OYO PLOTTER	1	ALLAN TERRIL	GEO/P/C
SSB RADIOS	2	ANALOGUE BOOMER		LURIE SKINNER	SURV.
DGPS SYSTEM	2	SYSTEM(SPARE)	1	LURIE ETHERIDGE	TECH.
PC NMN	2			ADRIAN STOLEZ	PROC.
AO PLOTTER	1				
DESO 20 E/S	2				
UNIBOOM	1				
231/232A	2				
DE2 PHT 1	1				
CONSUMABLES	1x 5GB QWEST DISK, 2x E/F ROCK				
VEHICLE					
ACCOMMODATION					

AUTHORISED CONTRACT CHANGES/COMMENTS

PARTY CHIEF'S SIGNATURE	CLIENT REPRESENTATIVES SIGNATURE	DOR
<i>Allan Terril</i>	<i>JNG</i>	2683



## ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT C.G.E.	JOB NO. 8428	DATE 28/8/91
LOCATION BONAVENTURE GULF	VESSEL PERSEPHONE	

FROM	TO	SUMMARY OF OPERATIONS
0007	0313	LINE TELLINE 1A. 21.25 km (135.35 km)
0313	1115	NO GPS WINDOW REST PERIOD HHS START UP SYSTEM
1203		LINE MOVE TO VICTORIA RIVER LOCATION.
	1115	START-UP SYSTEM
1203	1615	LINE VICTORIA 237.14 km (2172.75)
1615	2025	ON ANCHOR, ON LINE AWAITING SATELLITES
2025	2356	LINE VICTORIA STOP LINE TO RESET SOFTWARE AT 2400.
		22.06 km (194.81)

EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
ASHTech RCVRs	2	DYD PLOTTER	1	ALLEN TERRILL	GEO / PC
SSB RADIOS	2	ANALOGUE SYSTEM	1	LAWRENCE SKINNER	SURV.
DGPS SYSTEM	2			LEONIE ETTINGEDE	TECH
PC NAV	2			ADRIAN STOLEA	PROC.
AD PLOTTER	1				
DESO 20 E/S	2				
UNIBOOM	1				
231/232 A	2				
DEPTH 1	1				
CONSUMABLES		3 x 51/2" DISKS, 2 x E/S ROLL			
VEHICLE		1 x LG DYD ROLL			
ACCOMMODATION					

AUTHORISED CONTRACT CHANGES/COMMENTS

PARTY CHIEF'S SIGNATURE	CLIENT REPRESENTATIVES SIGNATURE	DOR
Allen Terrill	Joe	2684



## ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT	C.G.E.	JOB NO.	8428	DATE	29/8/91
LOCATION	BONAPARTE GULF	VESSEL	MERMAID REEFER		
SUMMARY OF OPERATIONS					
FROM	TO				
0000	0019	TURNING onto LINE			
0019	0311	LINE VIC #1 B.	24.74 km (219.55)		
0311	1125	WINDOW CLOSED REST PERIOD			
1125	1215	HP anchor head to LINE			
1215	1615	LINE VIC #C WITH <del>NOT</del> GOOD NAV.			
1615	1406	CONTINUE LINE VIC #C	14.34 (233.81)		
1421	1615	LINE VIC #2 WITH GOOD NAVIGATION	37.9 (271.79)		
1615	1808	CONTINUE LINE WITH POOR NAV FOR GEOLOGICAL TIE.			
1810	2040	CONTINUE LINE AS VIC #2 <sup>+ 2B</sup> AFTER NAV RESET, POOR NAV.			
2040		TURNING TO NEW LINE, SETTING UP DGPS			
2300		LINK PROBLEMS. 11.79 (283.58) 7.92 (291.5)			
2300		HEADING NORTH TO INVESTIGATE FLARES SIGHTED AT 2200 AND REPORTED TO DARWIN RADIO, <small>DGPS LINE BACK AT 233C.</small>			
EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
ASPECTECH RCVRS	2	DYD PLOTTER	1	ALAN TARDIFF	GEO / P/C
SSB RADIOS	2	ANALOGUE SYSTEM	1	Laurie Skinner	SURV.
DGPS SYSTEM	2			MURIEL EATHERIDGE	TECH.
PC NAV	2			ADRIAN SAROCCA	PROC.
HP PLOTTER	1				
DESO 20 E/S	2				
UNI boom	1				
231/232 A	2				
DEPTH I	1				
CONSUMABLES	2 1/2" DISKS, 1 - E/S ROLL				
VEHICLE					
ACCOMMODATION					

## AUTHORISED CONTRACT CHANGES/COMMENTS

*Alan Tardiff*

PARTY CHIEF'S SIGNATURE

CLIENT REPRESENTATIVES SIGNATURE

*Jug*DOR  
2685



## ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT	C.G.E.	JOB NO.	8428	DATE	30/8/91
LOCATION	VICTORIA RIVER	VESSEL	M-ACHIEVRER		
FROM	TO	SUMMARY OF OPERATIONS			
0000	0015	FLARES CONFIRMED BY DARWIN DUE TO AIRCRAFT. RETURN TO LINE.			
0015	0206	RETURN TO SOL.			
0206	0309	LINE VIC # 3	8.62	(292.2)	(299.77)
0309	1137	GPS WINDOW CLOSED, REST PERIOD, 1000CMG A-S.I.			
1137	1312	LINE VIC # 3A	11.05	294.63	(310.92)
1312	1354	CHARGE DGPS LORIC TO 4 MEG, RETURN TO LINE			
1354	1627	LINE VIC # 3B .	PULL CRAB		
1627		STEAM TO ORR RIVER MOUTH 20.65 (331.47)			
EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
DASHTECH RCI	2	040 PLOTTER	1	A TERRILL	geo/p/c
SS B'S	2	ANALOGUE SYSTEM	1	L SKINNER	SURV.
DGPS SYSTEM	2			L ETHERIDGE	TECH
PC NAV	2			A STANNERS	PROC.
AO PLOTTER	1				
DESO 20 E/S	2				
UNIBOAR	1				
231/232A	2				
DELPHI	1				
CONSUMABLES	1x SYNTH DISK, 1x E/S ROLL, 1+ SM.				
VEHICLE	040 ROLL.				
ACCOMMODATION					

## AUTHORISED CONTRACT CHANGES/COMMENTS

*Allan Terrell*

PARTY CHIEF'S SIGNATURE

CLIENT REPRESENTATIVES SIGNATURE  
*Jmf*DOR  
2686



## ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT	CGE	JOB NO.	8428	DATE	31/8/91
LOCATION	BONAPARTE BAY E	VESSEL	MERHAD Achiever		
SUMMARY OF OPERATIONS					
FROM	TO				
0800	0220	STEAMING TO CAMBRIDGE GEAR/OFF RIVER MOUTH .0220 ON ↗			
0220	1000	ON ↗. 0900 COM'S WITH TRUSCOTT + N.H.C CHECK 1000 UP ↘			
1029	1118	LINE 377500 7.06 km (338.53)			
1126	1235	LINE 378400 6.87 km (345.40)			
1258	1349	LINE 378500 (TOUCH BOTTOM AT 600) 5.99 km (351.3)			
1408	1503	LINE 379000 ↗ 6.53 (357.92)			
1510	1616	LINE 379500 7.83 (365.75)			
1616	1930	DGPS WINDOW CLOSED			
1930	2036	LINE 380600 (RERUN OVER 380000)			
2048	2144	LINE 380500A 7.23 (372.98)			
2203	2302	LINE 381000 8.28 (381.26)			
2314	2354	LINE 381500 (END TO RESET SOFTWARE AT 2400) 3.23 km (384.49)			
EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
ASHTECH RCVR	2	OYO PLOTTER	1	A TERRILL	Geo/P/C
SSB's	2	ANALOG SYSTEM/SPARE	1	L SKINNER	SURV.
DGPS system	2			L ETHERIDGE	TECH
PC NAV	2			A SAROLEA	PROC.
AO PLOTTER	1				
DESO 20 E/S	2				
UNIBOAM	1				
231/232 A	2				
DECPTH 1	1				
CONSUMABLES		2x540MB DISKS, 2x8/15 ROLLS			
VEHICLE					
ACCOMMODATION					
AUTHORISED CONTRACT CHANGES/COMMENTS					

PARTY CHIEF'S SIGNATURE

CLIENT REPRESENTATIVES SIGNATURE

DOR

2687



ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT	CGE	JOB NO.	8428	DATE	1/9/91
LOCATION		VESSEL	on ACHIEVER		
FROM	TO	SUMMARY OF OPERATIONS			
0005	0039	LINE 38/580A	3.63 km (383.12)		
0046	0146	LINE 382000	7.76 km (395.88)		
<del>0200</del> 0146	0900	Window (closed, rest period)			8
0900	1054	PREPARING FOR WORK, TUNING RADAR ETC.			
1054	1215	LINE 382500	8.34 km (404.22)		
1219	1318	LINE 383000	8.22 km (412.86)		
1325	1432	LINE 383500	8.27 km (420.71)		
1440	1544	LINE 384000	7.54 km (428.25)		
1554	1605	LINE 384500 ABORTED, window closed			
1605	1840	Window closed. Window opens with SV #24, previously u/s, now good.			
1840	2000	LINE 384500A	10.33 km (438.53)		
2020	2150	LINE 385000	9.69 km (448.27)		5.12 (457.46)
2158	2313	LINE 385500	9.19 (457.40) 239 - 2400 LINE 386000		
EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
ASHTEC RCR	2	DYO PLOTTER	1	A TERRIL	Geo/P/C
S.S.B's	2	ANALOG SPARE	1	L SKINNER	SURV.
DGPS system	2			L LETHERIDGE	TECH
PC NAV	2			A SAROLEA	PROC
AO PLOTTER	1				
DESO 20 B/S	2				
UNIBOOM	1				
231/230N	2				
DELP41	1				
CONSUMABLES		2-5MEST DOGS, 2xE/5ROLLS			
VEHICLE					
ACCOMMODATION					

AUTHORISED CONTRACT CHANGES/COMMENTS

PARTY CHIEF'S SIGNATURE	CLIENT REPRESENTATIVES SIGNATURE	DOR
Alan Yerrell	JW	2688



ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT	C G E	JOB NO.	8428	DATE	2/9/91
LOCATION		VESSEL	M. ACTIVER		

FROM	TO	SUMMARY OF OPERATIONS			
0001	0031	LINE	3860004	3.84	(466.42)
0039	0205	"	386500	9.31 km	(475.73)
0205	1037	on monitor, window closed + rest period			
1037	1148	LINE	387000	9.87 km	(485.60)
1155	1316	LINE	387500	10.03 km	(495.63)
1325	1420	LINE	388000	7.36 km	(402.99)
1425	1437	LINE	388000A	concentration line.	1.81 (404.80)
1445	1615	LINE	388500	10.25 km	(415.05)
1700	1833	LINE	389000	15.26 km	(430.31) 424.7
1846	2017	LINE	389500	12.12 km	(436.91)
2028	1054	LINE	390000	15.26 km	(452.17)
2300	2359	LINE	390500	RESET NAV. SOFTWARE	
					7.81 km (459.98)

EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
ASPECTEC RECVR	2	DYI PLOTTER	1		
SSB	2	ANALOG SPARE			
DGPS	2	SYSTEM.	1		
PC NAV	2				
AQ PLOTTER	1				
D80 20 E/S	2				
UNIBOOM	1				
231/232 A	2				
D62P14 1	1				
CONSUMABLES		3x5 QUEST DISCS 1xLARGE BYO ROLL			
VEHICLE		2x 6/8' ROSES			
ACCOMMODATION					

AUTHORISED CONTRACT CHANGES/COMMENTS

PARTY CHIEF'S SIGNATURE	CLIENT REPRESENTATIVES SIGNATURE	DOR
		2689



## ASSOCIATED SURVEYS

ACN 009 172 990

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT CGE(DEMOS)	JOB NO. 8428 (DEMOS)	DATE 2/9/91
LOCATION DARWIN	VESSEL M ACHIEVER / M SEARCHER.	

FROM	TO	SUMMARY OF OPERATIONS
0000	2600	DEMOB OF GEOPHYSICAL EQUIPMENT FROM ACHIEVER TO SEARCHER.
		MOB OF DGPS EQUIPMENT TO ACHIEVER FOR SANTOS RIG MOVE.
n 1100		CGE DATA AND DEPTH I DISPATCHED TO PERTH
n 1400		R WILLIAMS, B JACKSON ARRIVE DARWIN L ETHERIDGE DEPARTS FOR SYDNEY.
2 1800		A TERRILL, L SKINNER & STROCCAS DEPART FOR PERTH.
		THIS DOR MAY OVERLAP WITH DOR FOR SANTOS JOB - R. WILLIAMS PARTY CHIEF

EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
DEMOS.				DEMOS	
CONSUMABLES					
VEHICLE	+ 34				
ACCOMMODATION					

## AUTHORISED CONTRACT CHANGES/COMMENTS

PARTY CHIEF'S SIGNATURE	CLIENT REPRESENTATIVES SIGNATURE	DOR
Alia Terrell		4499



## ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT	CGE	JOB NO.	8428	DATE	3/9/91
LOCATION	BONAPARTE GULF	VESSEL	M. ACTIVER		
SUMMARY OF OPERATIONS					
0002	0034	LINE 390500A	64.01 km (463.99)		
0034	1138	ON ANCHOR, WINDOW CLOSED,	APPROX 1000 CALL PER 24H.		
1138	1406	LINE TELINE 2	18.33 km (482.32)		
1432		LINE 376000A	3.77 km (486.09)		
1515	1600	LINE 376500A	6.09 (492.18)		
1609	1621	LINE 326500B	1.58 (493.76)		
1621	1826	GPS WINDOW CLOSED.			
1826	2140	TELLINE 3	20.78 km (514.54)		
2152	2306	LINE 394500	28.72 km (514.54)		
2325	2359	LINE TELLINE 4. STOPPED NAV TO RESET AT 2400 hrs	4.78 km (528.04)		

EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
ASHTECH RCVRS	2	OYO PLOTTER	1	A TERRILL	GEO/P'C
SSB's	2	ANALOG BOARD		L SKINNER	SURV.
DGPS SYSTEM	2	(SPARE)	1	L EATHERIDGE	TERIT
PC NAV	2			A SAROLEA	PROC.
AZ PLOTTER	1				
DESO 20 E/S	2				
UNIBOAM	1				
231/232A	2				
DELPHI	1				
CONSUMABLES		25y 5gb disk, 25y E/S Rolls			
VEHICLE		16y small oyo roll			
ACCOMMODATION					

AUTHORISED CONTRACT CHANGES/COMMENTS

PARTY CHIEF'S SIGNATURE	CLIENT REPRESENTATIVES SIGNATURE	DOR
Allan Terrill	J Long	2690



## ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT	C.G.E	JOB NO.	8428	DATE	4/9/91
LOCATION	BONARATH GULF	VESSEL	MERMAID ACHIEVER		
SUMMARY OF OPERATIONS					
0001	0020	TIELINE 4A.	2.75 km (530.79)		
0020	1144	REST PERIOD, WINDOW CLOSED. PROCESSING DATA. PHONE ASI PERTH 10000.			
1144	1300	LINE 383000 B	9.77 km (540.56)		
1327	1452	LINE 391500	11.13 km (551.69)		
1505	1643	LINE 392500	11.79 km (563.48)		
1653	1819	LINE 393500	11.96 km (575.44)		
1836	2016	LINE 396000	12.71 km.		
2026	2100	Line 394500A	4.38km		
2108	2323	Tieline 5	11.87km		
2336	2359	Line 404000A	4.25km		
		STOP LOGGING TO REST 10-11			
		AT 2100			

EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
ASHTERK FCVR	2	040 PLOTTER	1	A TERRILL	Geo/P's
SSB's	2	ANTCOS SYSTEM	1	L SKINNER	SURV
DGPS	2			L ETHERIDGE	TECIT
PC NAV	2			A SAROCIA	PRO
A1 PLOTTER	1				
DESO 20 E/S	2				
UNIBeam	1				
231/2324	2				
DEPTH	1				
CONSUMABLES		1x SYQUEST DISK, 1xE/S ROLL			
VEHICLE					
ACCOMMODATION					

AUTHORISED CONTRACT CHANGES/COMMENTS

PARTY CHIEF'S SIGNATURE	CLIENT REPRESENTATIVES SIGNATURE	DOR
Allan Yerrell	Jmg	2691



ASSOCIATED SURVEYS

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT	CGE	JOB NO.	8428	DATE	5/9/91
LOCATION	BORAPA PLATE GULF	VESSEL	MERMAID Achiever		
FROM	TO	SUMMARY OF OPERATIONS			
0004	0110	LINE 404000 B.			
0110	0200	ATTEMPT VELOCITY PROBE, BAR CHECK TD 2-07 Vs 1530 (Assumed)			
0200		DEPART SITE FOR DARWIN.			
0900		COMMENCE BOOMER & NAV PROCESSING			
1000		PHONE ASI OFFICE BEGIN DEMOBBLING EQUIPMENT			
1400		PHONE ASI OFFICE			
2400		EN ROUTE DARWIN. FINANCING TRACK PLOT AND BATHY PROCESSING			
EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
ASHTECH REC	2	0YO PLOTTER	1	A TERRICE	GEO/P/C
SSB's	2	ANALOG BOOMER		L SCANNER	SURV
DGPS SYSTEM	2	(SINCE)	1	L LETHERIDGE	TECH
PC NAV	2			A STROCKA	PROC
A1 PLOTTER	1				
DESO 20 B/S	2				
UNIBOOM	1				
231/232 A	2				
DELPHI	1				
CONSUMABLES	1 SMALL ROLL 800 PAPER				
VEHICLE	48 P/C DISKS USED TO DATE				
ACCOMMODATION					

AUTHORISED CONTRACT CHANGES/COMMENTS

PARTY CHIEF'S SIGNATURE

CLIENT REPRESENTATIVES SIGNATURE

DOR

2692



## ASSOCIATED SURVEYS

ACN 009 172 990

## DAILY OPERATIONS REPORT (HYDRO)

CLIENT CGE. (DEMOB)	JOB NO. 5428	DATE 6/9/91			
LOCATION DARWIN	VESSEL MERMAID ACEEVER.				
FROM	TO	SUMMARY OF OPERATIONS			
0000	0700	UNDERWAY TO DARWIN.			
0700	1800	ALONGSIDE DARWIN, DEMOBILISING GEOPHYSICAL EQUIPMENT FROM MERMAID ACEEVER TO MERMAID SEARCHER. PACKING EQUIPMENT TO GO TO PERTH OR KARRATHA			
THIS WORK NOT RELEVANT TO CGE. THIS DOR FOR INTERNAL RECORDING PURPOSES ONLY.					
EQUIPMENT	NUMBER	EQUIPMENT	NUMBER	PERSONNEL	TITLE
DEMOB.				A TERRILL	
				L SKINNER	
				A ETHERIDGE	
				A SAROCHA	
CONSUMABLES					
VEHICLE	1 BUGGY HIRE S/WAGON.				
ACCOMMODATION	4 Rooms "FRONTIER TOP END"				
AUTHORISED CONTRACT CHANGES/COMMENTS					

PARTY CHIEF'S SIGNATURE

Allan Terrell

CLIENT REPRESENTATIVES SIGNATURE

DOR

4500



ASSOCIATED SURVEYS

GRL 2358

## GEOPHYSICAL RUN LOG

CLIENT: C.G.E.

JOB NO: 8428

LOCATION: CAMBRIDGE GULF

VESSEL: HERMANN REKHOV

SEA STATE

0000-0600

1200-1800

LOW SWELL, NEAR CALM

0600-1200

1800-2400

CALM

DATE	RUN NO.	START TIME	END TIME	START FIX	END FIX	DIRECTION	RECORD QUALITY — INDICATE VARIATIONS / CABLE OUT / FILTER SETTINGS ETC.				OPERATOR
							SYSTEM NO. 1	ROLL	SYSTEM NO. 2	SYNQEST DISK S	
25/8/91	345000	1446	1615	1	268	270	DELPH I / unboom 100 J.				CCE 9101
	377000	2125	2249	352	<del>602</del> 352	270	" " 200 J				
	376000	2302	2350	603	745	898	ABORT — EPHEMERIS CHANGE OVER				
26/8/91	375000	0025	0111	720	881	270°					
	376500	0128	0201	882	981	090°					
	405000	2113	2305	982	1203	270°	30 SECOND FIXES				CCE 9102
27/8/91	400000	0004	0249	1204	0534	090°					
	398000	1211	1329	1535	1693	270°	RECORD STARTED 1544, DIGITIZING 1550				CCE 9103
	403000	1410	1508	1694	1810	090°					
	404000	1520	1632	1811	1955	270°					
	380000	2030	2216	1856	2183	090°	Fit 2136 CHANGE TO DISK (CCE 9104 - Fit 2144 (2143 in tape))				(CCE 9104)
TIE LINE 1	2342	2134	2184	2219	343°		END LINE READY FOR 0000 SOFTWARE CHANGE 2359				



ASSOCIATED SURVEYS

GRL 2359

## GEOPHYSICAL RUN LOG

CLIENT:

CGE

JOB NO: 8428

LOCATION: GOODAPARTER GULF

VESSEL: MERRIMAC REEFIEVER

SEA STATE

0000-0600

CGE

1200-1800

0600-1200

1800-2400

DATE	RUN NO.	START TIME	END TIME	START FIX	END FIX	DIRECTION	RECORD QUALITY — INDICATE VARIATIONS / CABLE OUT / FILTER SETTINGS ETC.				OPERATOR
							SYSTEM NO. 1	ROLL	SYSTEM NO. 2	ROLL	
28/8	TIELINE 1A	0007	0313	2220	2591	343	LINE ENDED EARLY DUE SV'S CONST. MR LATER From NORTHING 8398000				DSC CGE9104 RANTO
	VIC#1	1203	1615	2592	2841	064°	Fix No on DEPTA EOC IS 2842 (PROBLEM AT 500?)				(GE9105)
	VIC#1A	2025	2356	2842	3083	4	60 SEC FIX. NO				(GE9106)
29/8	VIC#1B	0019	0311	3054	3228	4					APCH OVER AS VIBTRA-ARC (GE9107)
	VIC#1C	1215	1406	3229	3341	4		"	"		VICTRA-ARC "
	VIC#2	1421	1808	3342	3520	194°					(GE9108)
	VIC#2A	1910	2040	3571	3708	"	(STATION NO. VIC#2 ON DEPTA 1)				3627/3629 CHANGE DISK (GE9109)
30/8/91	VIC#3	0206	0309	3709	3773	053°					"
	VIC#3A	1137	1312	3774	3868	053°	(Fix 3974 is late)				"
	VIC#3B	1354	1627	3869	4022	53°					"



## ASSOCIATED SURVEYS

GRL 2360

## **GEOPHYSICAL RUN LOG**

**CLIENT:**

CCE

JOB NO: 8428

LOCATION: BONAPARTE GULF

VESSEL: M. AETHEVER

SEA STATE

0000-0600

1200-1800

0600-1200

1800-2400

DATE	RUN NO.	START TIME	END TIME	START FIX	END FIX	DIRECTION	RECORD QUALITY — INDICATE VARIATIONS / CABLE OUT / FILTER SETTINGS ETC.			DISK ROLL	OPERATOR
							SYSTEM NO. 1	ROLL	SYSTEM NO. 2		
3/8/91	377500	1029	1118	4023	4072	270°	FIRST FIX AND DEPTH IS 4023, FIXING MACED TO 4029 TO CATCH UP (NOT 4028)				CGE 9110
	378000	1126	1235	4073	4207	090°	FIRST FIX 4073 (NOT 4075) - FIXING OFF TO 4076 TO CATCH UP				
	378500	1243		4208		270°	Above 27				
	378500	1258	1349	4220	4321	090°					
	379000			4322		090°	Above 27				
	379400	1408	1503	4325	4435	090°					
	379500	1510	1616	4326	4517	270°	DISK FULL AT 4565				
	380500	1930	2036	4568	4694	270°	(SHOT ON 380000 NORTHING)				CGE 9111
	380500A	2048	2144	4700	4812	090					
	381000	2203	2302	4813	4931	270°					
	381500	2314	2354	4932	5012	090°					
	381500A	0005	0039	5014	5082	090°					
	382000	0046	0146	5083	5201	270°					CGE 912



ASSOCIATED SURVEYS

GRL 2361

## GEOPHYSICAL RUN LOG

CLIENT:

CGE

JOB NO: 8428

LOCATION: BONAPARTE GULF

VESSEL: M. ACHIEVER

SEA STATE

0000-0600

1200-1800

0600-1200

1800-2400

DATE	RUN NO.	START TIME	END TIME	START FIX	END FIX	DIRECTION	RECORD QUALITY - INDICATE VARIATIONS / CABLE OUT / FILTER SETTINGS ETC.				OPERATOR
							SYSTEM NO. 1	ROLL	SYSTEM NO. 2	ROLL	
1/9/91	382500	1054	1215	5202	5362	090°	Fix count problems to 5237 on DEPTH				DISK CGE9112
	383000	1219	1318	5363	5482	270°					A
	383500	1325	1432	5483	5619	090°					B
	384000	1440	1544	5620	5749	270°					DISK CCE9113
	384500	1554	1605	5748	5771	090°	ABORT - WINDOW CLOSED				
	384500A	1840	2000	5772	5932	090°	START ELCS AT 5777				
	385000	2020	2130	5933	6114	270°					
	385500	2158	2313	6115	6264	090°	Fix 6214/6217 CHANGE DISK. CONTINUE ON ELCS AS 385500A DISK CCE9114				
	386000	2319	2359	6265	6345	270°	HALT LINE TO RESET NAV. CONTINUES AS 386000 ON				
2/9/91	386000A	0001	0031	6346	6401	"	DEPTH 1. Fix count CORRECT AT 6349.				
	386500	0039	0205	6402	6573	090°					
	387000	1037	1148	6574	6713	270°	START ELCS 6577 AFTER COUNT PROBLEMS				A
	387500	1155	1316	6714	6838	090°	6834-6801-6804 CHANGE DISK.		6877/6878 TOGETHER		DISK CGE9115
	388000	1325	1420	6879	6989	270°	Fixing problems on NAV, FIXES RECALCULATED AT 6999. } RE-RUN CANT				
	388000A	1425	1437	7017	7017	090°	CONTINUE AS 388000 ON DEPTH. } RECOVER NAV				
	388500	1445	1615	7018	7196	090°	MISSED 7018 ON DEPTH, 7018 & 7019, 7019 IS NF 7020 OK.				
	389000	1700	1833	7197	7382	270°	DEPTH FIXING CORRECT AT 7201, MISSED 7197, 7198				



ASSOCIATED SURVEYS

GRL 2362

CLIENT:

C G E

JOB NO: 8428

## GEOPHYSICAL RUN LOG

LOCATION:

BonaSPARTE Gulf

VESSEL: M ACHIEVER

SEA STATE

0000-0600

1200-1800

0600-1200

1800-2400

DATE	RUN NO.	START TIME	END TIME	START FIX	END FIX	DIRECTION	RECORD QUALITY -- INDICATE VARIATIONS / CABLE OUT / FILTER SETTINGS ETC.				OPERATOR
							SYSTEM NO. 1	ROLL	SYSTEM NO. 2	ROLL	
2/9/91	389500	1544	2017	7383	7568	90°	PROCESSING AT 6000	Hz	SAMPLE	DISK CGE 9116	
	390000	2028	1054	7569	7859	270°	7858/7859 TOGETHER	"			
	390500	2300	2359	7860	7979	090°	RESET NAV AT 2400		CONTINUE AS 390500 ON DEPTH.	CGE 9115	
3/9/91	390500A	0002	0034	7981	8045	"	FIRST CORRECT FIX NO 7982 TO FIX NAV.		6-6 MB ON DISC		
	TIELINE 2	1138	8046		180°		ON DEPTH 1 FIX 8050 IS 8046, OFF TO 8051 TO CATCH UP.	8000 Hz		CGE 9117.	
	(TIELINE 2)	1406	8343	"			8320 DEPTH FIX COUNT OUT DUE PAPER CHANGE. (9 FIXES OUT) AT 8352 AT EOC.				
	376000A	1432	1504	8384	8405	090°	DEPTH DISK FULL AT 8404.			CGE 9101	
	376500A	1515	1600	8407	8501	270°				CGE 9104	
	376600B	1609	1621	8502	8526	"			"	"	
	TIELINE 3	1826	2140	8527	8915	000°	FIX 8527 SLIGHTLY LATE ON DEPTH 1			CGE 9118	
	394500	2152	2306	8916	9065	270°		6000 Hz		"	
	TIELINE 4	2325	2359	9066	9135	148°	MISSED FIXES 9066 & 9067 ON DEPTH,	9066 IS 9068, 9067/68 ARE NF		CGE 9116	
4/9/91	TIELINE 4A	0001	0020	9136	9175	"	RESET NAV FOR 2400	CONTINUE AS TIELINE 4 ON DEPTH 1.	"		
	388000B	1144	1300	9176	9177	090°				CGE 9106	
	67510	1323	1452	9221	9500	270°				CGE 9117	



## **ASSOCIATED SURVEYS**

GRL 2363

## **GEOPHYSICAL RUN LOG**

CLIENT: CFE JOB NO: 8428

JOB NO: 8428

LOCATION: Pontefract GUL F

VESSEL: M-ACHIEVER

#### SEA STATE

0000-0600

1200-1800

0600-1200

1800-2400



## SURVEY LOG RUN

CLIENT: CGE

JOB NO: 8428

LOCATION: CAMBRIDGE GULF

DATE	RUN NO.	START TIME	END TIME	START FIX	END FIX	RPM/SPEED	RAW DISC. NO.	ECHO ROLL NO.	DIRECTION	FILE LEAVE ON/OFF	COMMENTS	SURVEYOR
25/8/91	395000	1446	1615	1	268	4.0	#1	#1	270	CGEO1	ES/Boomer.	
	BANK	1620	1719	269	351	5.0	"	"	161	"	ES ONLY TO CHECK LEVEL OF BANK AT HIGH WATER.	
377000	2125	2049	352	602	3.6	"	#2	270	CGEO2	ENDLINE START AT (E425000 E)		
376000	2302	2350	603	745	4.0	"	"	90	"	i/2 LINE APPROX - 1866100 Premium. - lost - (POSSIBLE)		
376000A												
26/8/91	3750000025	0111	746	881	4.5	#2	"	270	CGEO3	ES/Boomer.		
	3765000128	0201	882	981	4.1	"	"	90	CGEO4	"		RAW
26/8/91	405000	2113	2305	982	1203	5.0	#2	#3	270	CGEO5 (Top 02)	(420,000 E - 405000 E) (30 SEC RX PING)	
27/8/91	4000000004	0219	1204	1534	142	#2	#3	"	90	CGEO6	(408,000 E - 430000 E)	
	398000	0211	1329	1535	1693	4.2	#4	"	270	CGEO7	(418000 E - 409500 E)	
	403000	0140	1508	1694	1810	4.9	"	#4	90	"	(408000 E - 416000 E)	
	404000	1520	1632	1811	1955	5.0	"	"	270	"	(408000 E - 416000 E)	
	380000	2023	1216	956	2182	3.0	#5	"	90	CGEO8	(416000 E - 425000 E) (TOP OF BANK)	
	TELINE#1	2312	1358	2184	2219	6.0	#6	"	343	CGEO9	TELINE	
28/8/91	TELINE#1AC007	0313	2220	2591	VALUES	#6	#5	343	CGEO10	Fx 2498 CANTER ROLL (END Nth 8398000)		
VIC#1	1203	1615	2592	2811	VALUES	#7	#5	64	CGE11	FIVE CGE11.RAW VRS collect plus horizon (ANNEST SCAN)		
VIC#1A	2025	2356	2842	3053	4.0	#8	#6	64	CGE12	SCANNING	START AT 04 36500 (ABT 500M O/HAP)	
29/8/91	VIC#1B0019	0311	3054	3228	4.5	#9	#6/	64	CGE13	SCANNING	START AT 04 57800 (ABT 1400M O/HAP)	



## SURVEY LOG RUN

CLIENT: CGE

JOB NO: 8428

LOCATION: BONAVENTURE GULF - MEXICAN RAILROAD.

DATE	RUN NO.	START TIME	END TIME	START FIX	END FIX	KNOTS RPM/ SPEED	DISC. NO.	ECHO ROLL NO.	DIREC- TION	RAW FILE HEAVE ON/ OFF	COMMENTS	SUR- VEYO.
29/8/91	VIC#1C1215	1406	3229	3314	3-8	#10	#7	64	CGE14		(START AT cat. 81565.8m)	
✓	VIC#2 11421	1808	3342	3570	5.0	#11	#7	194	CGE19	(GRAPHICS SIEVED) (SYSTEM FAILURE) (END OF LINE BAD)	(RUN THROUGH SATELLITE WINDOW LINES)	
✓	VIC#2A 1813	1928	3571	3648	4.0	#12	#7/#8	194	CGE16	(SYSTEM FAILURE)	" " " "	
✓	VIC#2B 1935	2040	3642	3708	4.0	#12	#8	194	CGE17	(GRAPHICS SIEVED) (SYSTEM FAILURE) (RECORDED FROM SCRATCH)	(ALL DATA TAKEN IN STAND ALONE MODE)	
										***** NOTE (CGE11.RAW / CGE15.RAW / CGE16.RAW / CGE17.RAW ALL CORRO.)		
30/8/91	VIC#3 0206	0309	3709	3773	4-4	#13	#8	53	CGE18		(END CAT 8600m)	
30/8/91	VIC#3A 1136	1312	3774	3869	4-4	#14	#8	53	CGE19			
*	VIC#3B 1354	1627	3869	4022	4-5	"	"	53	CGE19			
31/8/91	377500	1029	1118	4023	4072	4-2	#15	#9	270	CGE20	FIXING 60°	
	378000	1126	1233	4073	4207	4-0	"	"	90	"	FIXING 30°	
	378500	1247	1208	4209	"	"	"	270	CGE21	FIXING 30° ABORTED OFFLINE		
***	378500	1258	1349	4220	4321	4-0	"	"	270	"	FIXING 30°	
	379000	1400	1451	4322	4324	"	"	90	"	ABORTED OFFLINE		
***	379000	1408	1503	4325	4435	4-4	"	"	90	"		END BBS 425000
***	379500	1510	1616	4436	4567	3-3	#16	"	270	CGE22		START BBS 425000
	380500	1930	2036	4568	4699	11-0	#16	"	270	CGE23	ACTUAL NORTHING IS [ 8380000 ]	
	380500	2048	2144	4700	4812	4-0	#16	"	90	"		



ASSOCIATED SURVEYS INTERNATIONAL Pty. Ltd.

CLIENT: CAMBRIDGE GULF  
EXPLORATION.

JOB NO: WY 8428

0647

## SURVEY LOG RUN

LOCATION: CAMBRIDGE GULF - MERMAID Foothills.

DATE	RUN NO.	START TIME	END TIME	START FIX	END FIX	KNOTS RPM/ SPEED	DISC. NO.	ECHO ROLL NO.	DIREC- TION	RUN #	HEAVE ON/ OFF	COMMENTS	SUR- VEYO
3/8/91	381000	2203	2302	4813	4931	4.8	#16	#10	270	C6E31			
	381500	2314	2354	4932	5012	3.9	#17	#10	90	C6E25			
1/9/91	381500A	0002	0013	5013	5086	4.0	#17	#10	90	C6E26		{ SPLIT FILE over 2 hours LOGGING PROB!!	
	381500A	0005	0039	5014	5082	3.1	#17	#10	90	"			
	382000	0046	0145	5083	5201	3.9	#17	#10	270	"			
1/9/91	382500	1054	1113	5202	5362	4.0	#18	#10	90°	C6E27		(END EAST 417500) (START EAST 425500)	
	383000	1219	1518	5363	5482	4.0	"	#10	270	"		(START END 417300) (END 425500)	
	383500	1325	1432	5483	5619	3.5	"	#11	90°	"			
	384000	1440	1544	5600	5747	4.0	#17	#11	270	C6E28			
	384500	1554	1606	5748	5771	4.0	#17	#11	90°	"	4	ABORTED GPS WINDOW - ABNORMAL RECEIVER READS $\geq 35$	
	384500A	1840	2000	5772	5932	4.2	#19	#11	90°	C6E29		3 SV's. = PDR = 2.0 ( $\frac{GPS \text{ SWAP}}{\text{MIDLINE}}$ ) PDR = 2.0	
	385000	2020	2151	5933	6114	4.0	#19	#11	270	"		CFS ON - <del>SWAP</del> REAR MODE.	
	385500	2158	2313	6115	6264	4.0	#19	#12	90	C6E30			
	386000	2319	2359	6265	6345	4.5	#20	#12	270	C6E31		{ SPLIT FILE over 2 hours.	
2/9/91	386000A	0001	0039	6346	6401	4.2	#20	#12	270	C6E32			
	386500	0039	0205	6402	6573	3.9	#20	#12	90°	"			
	387000	1037	1147	6574	5710	4.0	#21	#12	270°	C6E33			
	387500	1154	1316	5711	6878	4.0	#21	#12	90°	"			
	388000	1325	1428	6879	6987	4.0	#21	#13	270	"	*****	LCMU SYSTEM HANGUP - 1420 hrs 6/12/00	



ASSOCIATED SURVEYS INTERNATIONAL Pty. Ltd.

0648

## SURVEY LOG RUN

CLIENT: CAMBRIDGE GULF  
Bathymetry

JOB NO: 444 8428

LOCATION: DONALDSON GULF - WORMANDA CREEK 2

DATE	RUN NO.	START TIME	END TIME	START FIX	END FIX	RPM/SPEED	DISC. NO.	ECHO ROLL NO.	DIRECTION	HEAVE ON/OFF	COMMENTS	SURVEY
2/9/91	388000A	1425	1437	6574	7017	4-0	#21	#13	290	66833	257W. (Fix 1's ALL OUT AT BEGINNING - 1000ft)	MAP
	388500	1445	1615	7018	7196	4-0	#20	#13	90°	66834	LAST 10MINS OF LINE IN BLOCKS W/IN	MAP
	389000	1700	1833	7197	7382	3-2	#22	#13	270	66835	.	MAP
	389500	1814	1821	7383	7503	4-0	"	#13	90	"	Two lines run out	MAP
	390000	2028	1055	7569	7859	4-0	#23	#13	270	66836	to 428000 ENDT	MAP
	390500	2300	2359	7860	7919	4-3	#23	#14	90	66837	SPLIT FILES OVER MIDNIGHT.	MAP
3/9/91	390500A0002	0033	7981	8048	4-0	#23	#14	90	66838	.	MAP	
	TIBLINE2	1138	1406	8046	8343	4-1	#24	#14	180	66839	.	MAP
	376000A	1432	1504	8344	8406	3-7	#24	#15	90	"	COMPLETE LINE TO 3425500	MAP
	376500A	1513	1600	8407	8501	4-5	#24	#15	270	66840	.	MAP
	376500B	1609	1621	8502	8526	3-8	#24	#15	270	66840	.	MAP
	TIBLINE3	1826	2140	8527	8915	4-0	#25	#15	360°	66841	.	MAP
	394500	2152	2306	8916	9065	4-0	#26	#15	270°	66842	.	MAP
	TIBLINE4	2325	2359	9066	9134	4-4	#26	#15	148	66842	SPLIT FILES AT MIDNIGHT.	MAP
4/9/91	TIBLINE400010020	9136	9175	4-6	#26	#15	148	66843	.	MAP		
	388000B	1144	1300	9176	9330	4-0	#26	#16	90°	66844	257W DUE TO NW. HAWG 219/91	MAP
	391500	1327	1452	9331	9500	4-0	#27	#16	270°	66845	.	MAP
	392500	1505	1643	9501	9697	4-0	#27	#16	90°	66845	.	MAP



**ASSOCIATED SURVEYS INTERNATIONAL Pty. Ltd.**


 CLIENT: CAMBRIDGE GULF EXPLORATION

JOB NO: 6448118

-0649

## **SURVEY LOG RUN**

LOCATION: MERRAUD AERIUS - BONAVENTURE GULF.



Date	Revision	Chkd	By	Date	Revision	Chkd	By



CAMBRIDGE GULF EXPLORATION NL  
18 HIGH STREET  
FREMANTLE W.A. 6160

VICTORIA RIVER  
PROSPECTIVE PALAEO-CHANNEL  
LOCATIONS AND  
SURVEY TRACKPLOT

Date SEPT 1991  
Scale 1:100 000  
Drawn A.L.S.  
Ref No. HY-8428  
Plan No. 8428-55 Rev.

Survey House, 18 Prince Street, West Perth  
P.O. Box 329, West Perth, W.A. 6005  
Tel (09) 322 4955 Fax (09) 322 1775

This document may only be used for the purpose for which it was commissioned and in accordance with the terms of engagement for the commission. Unauthorised use or distribution of this document in any form whatsoever is prohibited.