

1984 SIMPSON DESERT SEISMIC SURVEY

O.P. 184

NORTHERN TERRITORY, AUSTRALIA

FOR

BEACH PETROLEUM N.L.

BY

SEISCOM DELTA UNITED (AUSTRALIA) PTY. LTD.

NOVEMBER 1984

NORTHERN TERRITORY
GEOLOGICAL SURVEY

R285/81 A

TABLE OF CONTENTS

	Page
1. Introduction	1
2. Logistics and weather	2
3. Field Operations	6
3.1. general	6
3.2. surveying	7
3.3. reflection recording	11
3.4. drilling	14
3.5. uphole survey	15
4. Field office procedures	16
5. Conclusions	17

APPENDICES

- A. Equipment
- B. Personnel
- C. Operational Statistics
 - C.1. Recording
 - C.2. Drilling
- D. List of recorded lines
- E. List of permanent markers
- F. Intersection diagrams

ENCLOSURES

- Encl. 1. Location map 1:100,000
- Encl. 2. Horizontal loop closure map (no scale)
- Encl. 3. Vertical loop closure map (no scale)

LIST OF FIGURES

1. Location sketch
2. Survey location map
3. Field parameters
4. Uphole survey parameters
5. C.D.P. chart
6. Permanent markers

STATEMENT OF QUALITY

The survey reported herein has been conducted according to the standards specified in the contract governing the work. In the absence of such contractual standards, the survey has been conducted according to the current Technical Operating Standards of Seisoom Delta United (Australia) Pty. Ltd.

To the best of our knowledge and belief the survey included no deviations from the set standards, either of letter or spirit, which are not specifically reported or justified in the following pages.

SIGNED



AREA MANAGER , A.J. ATKINS



PARTY MANAGER , E. ALLWOOD

1. INTRODUCTION

In November 1984, Seiscom Delta United (Australia) Pty. Ltd.'s Party 4903 was contracted by Beach Petroleum N.L. to conduct a short seismic survey in O.P. 184, Northern Territory, using the Vibroseis* technique.

The proposed survey, named the 1984 Simpson Desert Seismic Survey, consisted of ten lines (an approximate 160 kilometre programme), radiating from 50 kilometres to 100 kilometres west and north of Poeppel Corner, in the Simpson Desert. Poeppel Corner is the monument established at the intersection of the states of Queensland, South Australia and the Northern Territory (latitude 26° south, longitude 138° east).

Line clearing began in mid-October 1984 with a survey advance party and the bulldozing crew plus equipment present in Birdsville (15th October). A Satellite Positioning unit was arranged by Beach to back up the field survey interpretation.

The first production profile was obtained on the 13th November, 84, instrument tests, hardwire similarities and experimental sweeps being recorded the day before. The last vibrator point was recorded on the 28th November, 1984.

An uphole programme of fifteen 50 to 60 metre deep holes was also proposed and a drilling crew mobilised from Brisbane to arrive in camp on the 11th November, 1984. Due to complicated field problems, this unit was not able to achieve the programme and another drilling crew was mobilised in early December, together with a set of DFS V instruments for the uphole recording.

The seismic recording acquisition was based on a kilometerage fee basis, and the line clearance was the responsibility of Beach Petroleum N.L.

2. LOGISTICS AND WEATHER

The area of operations lies in the Northern Territory, close to "Poeppel Corner", a survey monument established at the intersection of three states, approximately 134 kilometres west of Birdsville, Queensland. (Refer to figure 1).

Seiscom Delta United operated here in July - September 1979, but extending further west and using the "Geoflex" technique (refer to the relevant final report submitted).

The survey is located in the Simpson Desert itself and five of the ten assigned lines are located through the inter-dunes corridors. The other lines bisected the 30 metre high sand dunes, and only 4 or 6 wheel drive vehicles could move on the lines, where the soft sand required strong traction with or without sandtyres. As the "avalanche" side of the dunes faces east it is easier to travel from west to east, than east to west (the dunes are oriented NNW). The vehicles frequently became bogged to the axles, especially in the northern lines where the soft dunes were higher and wider (to 300m). The 4x4 water trucks suffered regular breakdowns, including snapped tail-shafts, but the 20 ton 6x6 wheel drive vibrators did extremely well. When travelling, a four wheel drive Toyota would average 25 kilometres per hour only, and other heavy trucks 15 to 20 kilometres per hour.

One major track, a rig road recently opened to connect Poeppel Corner's # 1 well onto the Birdsville track was the only main access to civilisation. This road, starting 65 miles south of Birdsville, more or less outskirted the dunes network and was in a very bad condition. The Caterpillar grader was employed for some days in its restoration, thus allowing the main recording trailers and crew vehicles to reach the only main camp location available; this was the well camp site (refer to figure 2), or to make the 14 hour round trip to Birdsville, some 380 kilometres.

Another possible access was Delhi QAA seismic line, a 1979 line ending near the prospect location, straight to Birdsville (168 kilometres), but cutting across the dunes network, with slow progress.

It was impossible to set up camp other than at the well site, and the first fly camp was established 54 kilometres north of the main camp. The access to the northern lines was by old 1964 C.G.G. Line Kl, which was also restored by the line clearing crew. The second fly camp was situated approximately 35 kilometres west, and was served by A.U.G. 1979-16 Geoflex line, but also difficult to drive on after restoration.

The drinking water was obtained from Birdsville using one of the single axle drill water tankers. This water had a strange colour and taste.

Other water for bath and drilling purposes was fetched from a filled stagnant depression found near the rig road, a 280 kilometres return trip requiring up to 10 hours driving. However, few trucks were initiated during the prospect for private use, the water being allocated for drilling firstly.

Normally, a truckload of food and other supplies was ferried from Brisbane to Birdsville at the beginning of the job.

Fuel was obtained in drums from the Mobil agent in Quilpie, Queensland, and the line clearing crew low-loader was used twice to pick it up from Windorah. The line clearing crew organised their own fuel.

Urgent parts deliveries were flown in by plane - Beechcraft Barons, from Coddair airline, using the good landing strip close to the main camp site. Three flights were chartered during this short job.

The recording crew mobilised on the 6th November, 1984 from another contract near Rolleston, Queensland. Appendix A lists the equipment.

The days were hot, up to 45°C outside, but readings of 50°C (maximum range of the camp thermometer) were recorded inside the vans during day time. Surprisingly enough the weather cooled off on the 22nd November with a gale force wind bringing rain clouds. A shower fell during the night (approximately 4mm) and a lower temperature of 10°C was read in the early morning of the 23rd November. However, after this change, hot weather soon built up again and was constant to the end of the survey. Strong winds & blowing sand occurred regularly during the survey, and the heat was very uncomfortable.

3. FIELD OPERATIONS

3.1. General

A survey team departed from Brisbane to arrive in Birdsville on 11th October, 1984. A few days were spent at Birdsville awaiting the line clearing equipment, which had to come from Millmerran (near Toowoomba, Queensland). The line clearing contractors, E.R. & C.B. Sweedman used their own low-loader twice for the transportation of the 2 Fiat-Allis 14C bulldozers, and hired a spare truck for the transport of the 4-wheel drive Caterpillar grader. Due to the very poor roads, cracking was caused to tanks and 2500 litres of fuel were lost on the way to Birdsville.

This crew arrived at Poeppel Corner's # 1 well site on 17th October, to find that line 1964 C.G.G. K1, the only access to the northern part of the prospect was in an untrafficable state. It took 4 days to restore the 54 kilometre access to line SD 84-39, and line clearing finally began on 24th October, 1984. The cutting progress was slow, line SD 84-39 bisecting the sand dunes orientation (refer to figure 2), and production on this line then stopped for a couple of days at the end of October, as the crew ran out of water in the very hot climate. Normally an A.C.E. drill water truck was sent in advance to assist this crew, but it broke down on its way up on this occasion and was later transported on a hired carrier to the camp site for repair.

Production started again on the 2nd November and the two machines had great difficulty in cutting the lines. As production remained slow accross the dunes, longer working days were initiated and the line clearing programme was achieved without major problems on the 24th November for the second dozer. The lead dozer had finished up on the 20th November.

The grader was only used over a few days for works on the rig road, when it became deeply bogged on the first sand dune off the camp, and remained there until the line clearing crew demobilised. A 6-wheel drive grader is recommended for future work in the area.

The line clearing production breakdown is approximately as follows :

Grader hours (rig road)	44.75 hours
1st bulldozer	283.50 hours
2nd bulldozer	307.00 hours
Total bulldozer	590.50 hours
cutting time (approximately)	447.00 hours
walking, towing, unbogging trucks	143.50 hours

From the approximate figures above-mentioned, many hours were spent in walking through the prospect due to the programme itself, as well as in opening accesses. Some hours were devoted to towing the seismic trucks accross difficult sand dunes. A D6 or equivalent crawler on duty for such a task should be envisaged for future work as the 1979 report also mentions, as well as a suitable tractor for towing duties in such treacherous sands.

3.2. Surveying

Survey works were carried out using WILD T-16 theodolites coupled with RED 1-A Sokkisha Electronic Distance Measuring apparatus (EDM). The surveyor set out the line by using solar observations corrected into grid bearing.

The chaining crew established the stations using a 60 metre long chain made from plastic coated multi-strand steel wire cables. This chain was regularly checked against a fibreglass tape measure for accuracy.

All V.P. locations were identified by white numbered pegs, the odd stations being marked with flagging. Low peg numbers started a line at any south or western ends.

Mud maps describing the features of the lines were drawn up and despatched to all sections of the crew.

All pegs were left in the ground.

The lines were permanently marked using steel pickets. An aluminium tag, dye stamped with all pertinent information was bolted on. (Refer to figure 6 and appendix E, and enclosure 1). The permanent markers were planted at a minimum of 5 or 3 kilometre intervals.

Levelling of line 84 SD 39 was done at every station (30m intervals) plus any intermediate change of grades, as the line cuts the dunes at right angles. All other lines were levelled at the V.P. locations plus any other changes of grader (tops and bottoms of sand dunes). The majority of these lines run in the dune corridors.

Procedure

Trigonometric levelling was done using :

- one face left reading of the 2 metre high prism
- one face left reading of the 5 metre high staff
- one face right reading of the 2 metre high prism
- one face right reading of the 5 metre high staff

These four readings were systematically done at the backsights, foresights and control points. Single face left face readings were obtained for the intermediate stations.

EDM measurements were used for backsights, foresights and control points with chainage accepted for intermediates.

Solar observations were taken at the beginning and the end of all lines, and many other check points along the survey. These solar observations were not restricted to a set number, as many more sun shots were taken as part of Seiscom's survey standards.

All computations were done using a Northstar Advantage 64k computer, and Hewlett Packard calculators. A first set of provisional values was obtained, the final being calculated on receipt of the Doppler station value.

Normally a first processing run was done by entering the 2 metres heights readings, then a second run was processed with the 5 metres ones. The comparison of both results ascertained the accuracy of the levelling and a set of provisional values was edited.

A report summing up the production of the entire survey section was submitted on a daily basis.

Primary Control

A Beach satellite positioning unit was to arrive at the early stage of the prospect. The technician, busy on another commitment, was not able to arrive until the 22nd November. The base station was set up at Poeppel Corner and 2 translocations were set up before the base station Magnavox MX 1502 Geociever broke down. The technician withdrew from the crew on the 27th November. The final computations were achieved using these 2 values only.

A tie between south of 84 SD 44, going through the eastern end of SD 79 23 and connecting north of 84 SD 101 was achieved.

Loop Closures

Lines SD 84 39, 38, 40, 42, 44, 101, 41, 43 and 45 are based on Doppler station # 2. A tie to old permanent marker I/S 72.5 and 79/16 gives a misclose of -55.98, -24.21 and + 5.77 and a check tie to the old P.M. I/S 79.17 and 72.5 gives a misclose of - 80.32, - 36.81 + 5.80.

Line SD 84-46 is based on Doppler station # 1 and tie to old P.M. I/S K1 and 79/21 gives a misclose of - 33.39, -45.26 and + 5.96.

From these results it seems that the height datum for the 1979 survey is in error by approximately 5.86 mt. The co-ordinate tie is reasonable as the 1979 survey was run by stadia and no scale factor applied; so one would expect the misclose to increase as the distance from Poeppel Corner increased.

Differences in double runs only are shown on the two loop closure maps for the sake of clarity. If further information is required see the work sheets in the relevant files.

The double runs all close well and the connection to old P.M.s are of a constant nature.

3.3. Reflection Recording

The parameters used were obtained after a short series of experiments carried out on the 12th November, and are as follows :

Number of traces	:	96
Coverage	:	1200%
Geophone group interval	:	30m
Geophone type	:	GSC 20D, 10Hz, 70% dumping Coil resistance 395 ohms
Spread	:	1500-90-0-90-1500 m
Geophone array	:	12 phones equally spaced and centred on peg
Geophone spacing	:	2.5m
Geophone array length	:	27.5m
Source (refer to figure 3)	:	4 vibs. in line
Number of sweeps	:	6 for 84 SD 39, 8 for all other lines
Sweep frequency	:	from 16 Hz. to 96 Hz.
Sweep length	:	6 sec.
Listen time	:	4 sec. total 10 seconds
Mode	:	Logarithmic
Distance between pads	:	10m in line
Pad move up	:	5m for 84 SD 39 4m for all other lines
Vibrator array length	:	55m for 84 SD 39 58m for all other lines
V.P. interval	:	120m
Filters - low	:	out
- high	:	128 Hz.
- notch	:	out
Gain constant	:	48 db.
Sampling rate	:	2 ms
Tape format	:	SEG B, 1600 BPI, uncorrelated SEG Y, 1600 BPI, correlated with zero phase filter

Auxillary channels : 1 timing word
 2 unfiltered pilot sweep
 3 unfiltered pilot sweep
 4 radio similarity
 5 time break

Note : The zero phase filter is built up after each
 initialisation of the entire system.

The first line was vibrated with 6 sweeps. It was
then decided to switch to 8 sweeps as a safeguard
for a shallow refractor.

Daily tests, including hardwire similarities were carried out at the start of each day. Monthly tests were also produced for further assessment to our office in Singapore at the commencement and end of the job.

The hardwire similarities were considered as good when all the vibrators were in phase within 700 milliseconds.

Normally the recording truck would set off the line, using 1000 feet long jumper cables to connect onto the spread. This was not always possible because of the sand dunes.

Reflection recording began on the 13th November, line 84 SD 39, western end. The first fly camp was set up near the intersection with 1964 Kl. The northern part of the prospect was recorded on the 21st November, and the second fly camp was established along line 84 SD 101 that day.

Recording production went smoothly, in spite of the difficult sand dunes to operate, ie. 18 kilometres were recorded on the 23rd November, this including a change of line and extremely hot weather.

A Vigilant system operated throughout the prospect. Readings of the SEG Y (demultiplexed) tapes were done, and crude velocity analysis were also processed to obtain a 1200% raw stack (no static correction). Good results were obtained, and interesting events emerged. The rather low velocity functions applied needed constant monitoring in this basin, and re-run stacks showed better organised reflectors by only using finer functions.

3.4. Drilling

An A.C.E. Drilling crew mobilised from Brisbane on the 6th November, 1984 to reach camp on the 11th November.

A Midway all hydraulic rig was assisted by 2 Toyota 7 tonnes water trucks.

A series of unfortunate events prevented this crew from performing as expected, ie : the drilling rig broke a compressor air intake at the start of the job and the Seiscom Delta United 4x4 water truck was allocated to this crew to replace the Toyota truck, but continually snapped tail shafts when operating on dunes, thus restricting the drilling water supply. Casing was almost impossible to achieve and 2 x 200 feet holes were lost. However, the drilling crew tried extremely hard to drill and perform. They left the prospect on the 26th November.

To remedy the drilling problem, Seiscom Delta United mobilised one of its own drilling crews which had been operating in the Cooper Basin.

Two Mayhew 1000 and supporting water trucks arrived at the camp site on the 2nd December and started drilling at uphole no. 2 on the 3rd December. Vast quantities of water were used (mud bit drilling or lost circulation) and the last hole was achieved on the 7th December. The drillers reported a fair drilling production in the top layer of loose sand followed by clay (constant lithology in every hole sand-clay).

3.5. Uphole recording

Uphole recording began on the 3rd December to end on the 7th December. Harnesses fabricated to the depths requirements were primed with "A" or "D" boosters at 5 metre intervals. The top charge (3m) was one detonator only. A DFS V instrumentation with standard I/O encoder-decoder was used.

Uphole No.	Location	Drilled	Loaded	Elevation	Remarks
1	INT SD 38/SD39	48m	45m	56.65	Corridor
2	INT SD 39/SD40	66m	60m	57.21	Dune slope
3	INT SD 39/SD42	54m	50m	56.41	Nearly flat
3A	SD 39 VP 396	66m	60m	68.56	Top of dune
4	INT SD 39/SD44	54m	50m	61.44	Dune slope
5	SD 38 VP 168	54m	50m	47.53	Flat area
6	SD 40 VP 188	54m	50m	51.48	Flat/top dune
7	SD 42 VP 192	54m	50m	50.05	Dune slope
8	SD 44 VP 620	54m	50m	46.04	Flat area
9	SD 44 VP 132	54m	50m	42.53	Flat area
10	SD 41 VP 224	54m	50m	47.01	Top of dune
11	INT SD 101/SD 43	54m	50m	60.30	Top of dune
12	INT SD 101/SD 45	66m	60m	41.82	Dune slope
13	INT SD 46/SD 21	66m	60m	35.90	Dune slope
14	SD 46 VP 168	66m	60m	40.33	Dune slope

(Uphole 3A, close to 3 was added, and specially located on top of a sand dune for investigation).

The results obtained were good and all documents were despatched to the processing centre for static computation. The rough field plots kept in the field office confirm more or less the 1979 survey refraction data (one or two layers of similar velocities) with the exception that the consolidated layer may not be a flat plane underlying the dunes as thought in 79. Uphole at SD 101, VP 224, located on top of a dune yields only 22m of weathering. Uphole no. 13 at intersection of lines SD 46/SD 21 drilled on the slope of a dune gives only 13m of Dw when the average depth of the weathered layer is of 25m approximately. A more detailed static control program may be necessary for future surveys.

4. FIELD OFFICE PROCEDURES

Reports from all sections of the crew were received at the field office and a daily report was transmitted to Seiscom Delta United's Brisbane office, and was also submitted to Beach Petroleum N.L. representative in the field, Mr. D. Gray, for endorsement.

All tapes (SEG Y) were despatched to Seiscom Delta United's processing centre in Melbourne, together with the relevant observer reports.

5. CONCLUSIONS

The 1984 Simpson Desert Seismic Survey, using the Vibroseis technique, proved a production success in spite of the difficult terrain operated on, and the very hot climate at this time of the year.

The areas investigated yielded good data quality, but most importantly, in locations of the Pedirka Basin where very little seismic research has been carried out to date. The basic seismic acquisition was achieved according to plan.

Seiscom Delta United is most appreciative of the assistance of Mr. D. Gray, representative of Beach Petroleum N.L.

Respectfully submitted by



R.A. Ashton

Operations Supervisor

SEISCOM DELTA UNITED (AUSTRALIA) PTY. LTD.

A P P E N D I X A

EQUIPMENT

RECORDING EQUIPMENT

96 channel DFS V system
Texas Instrument TIMAP FT-1 system
Texas Instrument Vibrator Electronics, VC III
SIE ERC 10C 64 channel electrostatic camera
Rollalong switch and other auxillary input equipment
Full spare kit, oscilloscope, geophone tester etc.
300 strings of geophones, 12 geophones per string, GSC 20D, 10Hz.
36 Mark product cables, 104 pair cables, 8 takeout, Terracon heads.
2 x 150m jumper cables
2 x 50m jumper cables
One GMC Sierra 4x4 truck with air conditioned recording cabin
4 Toyota Landcruiser 4x4 geophone/cable trucks
1 Toyota Landcruiser 4x4 personnel carrier
1 International 4x4 cable truck
FM radios
SSB radios (operating frequency 7770 Khz)
1 37.5 KVA generator mounted on recorder truck

SOURCE EQUIPMENT

5 Mertz model 12 vibrators, mounted on 6x6 International Paystar
5000 trucks (20 ton unit), fitted with Michelin tyres.
Vibrators fitted with MOOG high frequency valves from 5Hz to 250Hz
with peak output of 30,000 lbs.
All trucks fitted with power winch, air-conditioned cabin.

OTHER

All supplies and parts, mechanical, survey, camp, recorder and office.

One Vigilant system mounted on a 4x4 Ford, 7 ton, truck with its own 20KVA generator.

SURVEY EQUIPMENT

3 WILD T-16 theodolites

2 Electronic Distance Measuring apparatus

Chaining equipment

1 Northstar Advantage Microcomputer, VDU terminal and line printer

3 Toyota Landcruisers 4x4

SSB Radios, walkie-talkies

Tools, chainsaws, etc.

Survey notes, calculators, etc.

CAMP EQUIPMENT

1 Party manager/assistant office trailer

1 survey office/cable repair shop trailer

1 mechanic workshop, power tools, welder, compressor, parts

1 shower/laundry trailer

5 sleeper trailers (8 man each)

1 kitchen trailer with cold room

1 diner trailer

1 mess trailer

2 50KVA generators

CREW SUPPORT VEHICLES

- 1 Toyota Landcruiser 4x4 - party manager
- 1 Toyota Landcruiser 4x4 - vibrator mechanic
- 1 Toyota Landcruiser 4x4 - camp supply
- 1 Toyota Landcruiser 4x4 - camp mechanic
- 1 International 4x4 water truck with water pumps, and high pressure pump
- 1 Bedford 4x4 vibrator support truck with crane and fuel tank
- 1 Bedford 4x4 camp support truck

DRILLING EQUIPMENT (A.C.E. Drilling, Brisbane)

- 1 Midway air-water drilling rig (weight : 20 tons) International truck with sand tyres
- 2 x 1000 gallon water truck (Toyota 7 tonnes 2 x 4)
- 1 4x4 Toyota

DRILLING EQUIPMENT (Seiscom Delta United)

- 2 x Mayhew 1000 air-water drilling rigs (1 for spare)
- 3 x 850 gallon 4x4 water trucks
- 1 x self contained field camp
- 1 4x4 Toyota/Recorder with DFS V instrumentation, encoder-decoder and uphole equipment

A P P E N D I X B

PERSONNEL

Party Manager	E. Allwood
Clerk	W. Bell
Vigilant/Seismologist	R. Vincart
Senior Observer	A. Kopij
Observer	G. Ziebarth
Senior Surveyor	T. Sheppard
Surveyor	R. Percy
Vibrator Mechanic	A. Smylie, B. Clarke
Vibrator Drivers	G. Cowell (Headman)
	S. Geal
	D. Columbus
	J. Blackley
Camp Mechanic	J. Healey
Head Linesman	D. Smith
Linemen	8
Chainmen	J. Gleeson, T. Harbottle
Rodmen	M. Dagg
Survey Helpers	1 (part time)
Cook	I. Rodgers
Camp Helpers	2
Uphole Observer	B. Holmes
Preloader/Shooter	D. Sulley
Sub-Contractor Surveyor & his rodman	M. Williamson
	M. Schwikowski
ACE Drilling, Brisbane - driller	K. Hardwick, plus 2 offsiders
Seiscom Delta United Drilling, - Brisbane	M. Johnson, Chief driller, plus 2 drillers, 3 helpers, 1 cook
Line clearing crew (E.R. & C.B. Sweedman)	5 men
Satellite Positioning Service	M. Bennet, Manager

APPENDIX C.1

OPERATIONAL STATISTICS

RECORDING

Recording personnel left Rolleston	5 November, 1984
Arrived Birdsville	9 November, 1984
Arrived campsite	11 November, 1984
Fly camp no. 1 established	13 November, 1984
First production profile	13 November, 1984
Last production profile	26 November, 1984
Days vibrating	12 ½ approximately
Shifts between lines	1 ½ approximately
Total	14 days
Kilometerage	157.68
No. of VP's	1324
Working time *	141.99
Travel time *	29.74
Total time	171.73
Production (158km ÷ 14)	11.3 km/day
Production (157.68 ÷ 171.73)	0.92 km/day
Production (157.68 ÷ 141.99)	1.11 km/day

* Working time includes 2.25 hours of tests

Travel time includes camp shifts

APPENDIX C.2

DRILLING

A) ACE DRILLING, BRISBANE

Left Brisbane	6 November, 1984
Arrived Birdsville	10 November, 1984
Rig on uphole site	12 November, 1984
Standby water truck (4 wheel drive)	13,14,15 November, 1984 17,21,22 November, 1984
Drilling	16,18,19,20 November
1st hole (UH No. 3)	50 feet caved in
2nd hole (UH 3A, top of dune)	20 feet caved in
3rd hole (UH 3) air and water	140 feet caved in
4th hole (UH 3) mud pit	200, lost circulation at 80ft. then PVC casing stuck at 40ft.
5th hole (UH 3A) mud pit, top of dune	200 feet, casing stuck at 85ft.
6th hole (UH 7) mud pit	200 feet, abandoned, water truck down
Drilling time (6 holes)	24 hours
Travel time (6 holes)	29 hours
Consumables	
Quick trol	5 bags
Quick mud	4 litres
1 set of Chevron blades	

A P P E N D I X C.2

DRILLING

B) SEISCOM DELTA UNITED (AUSTRALIA) PTY. LTD.

Arrived Birdsville	1 December, 1984
Left Poeppel Corner	8 December, 1984

Number of holes	15
Meterage	864 m
Average drilling time per hole (mud bit drilling)	1.50 to 2.00 hours

Consumables

12 bags mud
5 bags bran
5 bags Quick-trol

Uphole Consumables

"A" Boosters	240
"D" Boosters	24
1.8m detonators	161
Star pickets	15 + 15 weights
Insulating tape	16
Bailing twine	5 reels
Twin Flex	14 reels

A P P E N D I X D

LIST OF RECORDED LINES

Date	Line No.	VP	to	VP	No. of VPs	Kms
13,14 Nov	84 SD 39	76		952	220	26.28
15,16 Nov	84 SD 38	868		100	193	23.04
17 Nov	84 SD 40	600		120	121	14.40
18 Nov	84 SD 42	600		124	120	14.28
19-21 Nov	84 SD 44	1200		64	285	34.08
22-23 Nov	84 SD 101	530		58	119	14.16
23 Nov	84 SD 45	104		296	49	5.76
24 Nov	84 SD 43	100		332	59	6.96
24 Nov	84 SD 41	96		328	59	6.96
25 Nov	Move accross to line SD 46 all day					
26 Nov	84 SD 46	492		100	99	11.76
					<hr/> 1324	<hr/> 157.68 kms

Note : Sweep tests done on 12 November, 1984

Pegging Convention was for low number at any north or west ends.

A P P E N D I X E

LIST OF PERMANENT MARKERS

LINE/VP	EASTING	NORTHING	ELEVATION	REMARKS
<u>Line 84 SD 46</u>				
492	793 526.67	7 133 412.88	37.21	E.O.L.
468 (I/S 79.21) Doppler Station # 1	793 754.33	7 132 727.48	35.90	
352	794 849.48	7 129 416.24	34.66	
248 (I/S 79.QAF)	795 834.39	7 126 447.49	35.20	
148	796 776.60	7 123 591.20	44.55	
100	797 236.02	7 122 222.58	47.30	S.O.L.

Existing Permanent Markers

I/S K1 & SD 79.21 (384 120 MW)	795 814.39	7 133 357.26	18.34	
SP 690 line 79.QAF	795 894.47	7 126 454.72	39.34	

Line 84 SD 45

296	768 356.48	7 136 769.11	64.26	E.O.L.
168 I/S 84 WMZ 740	764 563.47	7 137 399.08	28.97	
Thomas # 1 well	764 596.85	7 137 385.51	28.56	
148 I/S 84 SD 101	763 971.03	7 137 497.03	41.82	
104	762 666.87	7 137 710.62	38.91	S.O.L.

Existing Permanent Markers

I/S 72.5 & 84 WMZ 740	764 600.85	7 137 452.63	28.90	
B.M. Thomas # 1	764 651.19	7 137 508.84	30.50	

LINE/VP	EASTING	NORTHING	ELEVATION	REMARKS
---------	---------	----------	-----------	---------

Line 84 SD 43

332	768 824.40	7 141 334.07	45.28	E.O.L.
208 (I/S 101 & 43	765 165.23	7 142 030.66	60.30	
100	761 979.04	7 142 633.41	30.02	S.O.L.

Existing Permanent Markers

I/S 79.17 & 72.5	762 656.68	7 142 567.19	33.80	
------------------	------------	--------------	-------	--

Line 84 SD 41

96	763 046.91	7 149 047.86	57.79	S.O.L.
224 (I/S 101 & 41)	766 768.73	7 148 093.28	47.01	
328	769 792.87	7 147 313.44	39.24	E.O.L.

Line 84 SD 101

530	767 357.02	7 150 327.73	53.54	E.O.L.
453 (I/S 101 & 41)	766 768.73	7 148 093.28	47.01	
292 (I/S 101 & 79/17)	765 528.76	7 143 420.47	77.87	
244 + 4mt. (I/S 101 & 43)	765 165.23	7 142 030.66	60.30	
100 + 20mt. (I/S 101 & 79/16)	764 068.22	7 137 861.34	36.23	
88 + 4 mt. (I/S 101 & 45)	763 971.03	7 137 497.03	41.82	
58	763 738.59	7 136 621.90	34.67	S.O.L.

Existing Permanent Markers

(I/S 72.5 & 79/16)	764 537.98	7 137 994.21	28.63	
--------------------	------------	--------------	-------	--

LINE/VP	EASTINGS	NORTHING	ELEVATION	REMARKS
---------	----------	----------	-----------	---------

Line 84 SD 44

1200	762 536.29	7 187 586.72	58.07	E.O.L.
1176 & I/S 44 & 39	762 785.85	7 186 910.90	61.44	
1100	763 580.67	7 184 769.64	53.26	
1000	764 626.73	7 181 952.51	70.38	
900	765 673.90	7 179 134.84	61.55	
800	766 718.16	7 176 316.23	52.25	
698	767 781.41	7 173 440.50	53.31	
600	768 813.85	7 170 680.96	45.24	
500	769 870.01	7 167 866.63	51.79	
400	770 925.02	7 165 052.73	47.13	
300	771 979.16	7 162 237.14	52.17	
200	773 033.13	7 159 420.70	51.98	
100	774 089.94	7 156 607.36	48.31	
66	774 449.25	7 155 650.85	48.81	

Line 84 SD 42

600	770 506.87	7 190 758.00	58.89	E.O.L.
576 (I/S 39 & 42)	770 736.49	7 190 074.79	56.41	
424	772 180.73	7 185 742.50	61.69	
272	773 618.65	7 181 407.57	61.07	
124	775 029.86	7 177 190.08	48.22	S.O.L.

Line 84 SD 40

600	780 087.08	7 194 552.62	55.69	E.O.L.
576 (I/S 39 & 40)	780 369.00	7 193 889.71	57.21	
412	782 407.81	7 189 403.06	69.73	
248	784 450.16	7 184 916.52	57.33	
120	786 043.96	7 181 415.78	46.55	S.O.L.

LINE/VP	EASTING	NORTHING	ELEVATION	REMARKS
---------	---------	----------	-----------	---------

Line SD 84 38

868	782 192.90	7 204 328.81	58.73	E.O.L.
685	784 358.74	7 199 274.82	67.48	
568 (I/S 38 & 39)	785 747.66	7 196 045.61	56.65	
404	787 685.88	7 191 513.51	54.52	
252	789 482.70	7 187 312.66	49.03	
100	791 278.58	7 183 110.67	50.18	S.O.L.

Line SD 84 39


76	762 003.69	7 186 599.69	52.55	S.O.L.
198	765 409.85	7 187 953.89	73.28	
299	768 231.93	7 189 075.96	65.94	
432	771 941.74	7 190 550.91	74.89	
542 (I/S 39 & K1)	775 009.09	7 191 761.73	57.15	
632	777 522.86	7 192 758.21	73.40	
734(I/S 39 & 40)	780 369.00	7 193 889.71	57.21	
828 + 16 mt.	783 001.37	7 194 939.29	71.17	
927 + 8.5mt. (I/S 39 & 38)	785 747.66	7 196 045.61	56.65	
952	786 437.17	7 196 319.83	54.48	E.O.L.
950 Doppler # 2	786 381.43	7 196 297.49	53.72	

A P P E N D I X F


INTERSECTION DIAGRAMS

INTERSECTION DIAGRAMS


SD84-46




SD84-39



SD84-42




SD84-40




INTERSECTION DIAGRAMS


SD84-38




SD84-44



SD84-101




SD84-41




INTERSECTION DIAGRAMS

SD 84 - 43




SD 84 - 45



SIMPSON DESERT 1984

LOCATION SKETCH



0 300 kms





FIG. 2

SIMPSON DESERT 1984

SURVEY LOCATION MAP

(O.P. 184)


1 : 250 000 approx.




SIMPSON DESERT 1984

FIELD PARAMETERS

SPREAD




GEOPHONE ARRAY



VIBRATOR ARRAY


SWEEP



arrays centred on V.P. peg

SIMPSON DESERT 1984


UPHOLE PARAMETERS



X	3 m	= I det
X	5 m	I A
X	10 m	"
X	15 m	"
X	20 m	2 A
X	25 m	"
X	30 m	"
X	35 m	"
X	40 m	"
X	45 m	"
X	50 m	I D
X	55 m	"
X	60 m	"


SIMPSON DESERT 1984

C.D.P. CHART




SIMPSON DESERT 1984

PERMANENT MARKER



aluminium tag



SDU : SEISCOM DELTA UNITED

84SD 39 : survey line number

E.O.L , S.O.L. end or start
of line

I / S : intersection

VP 150 + 32 W : VP number ,
distance and direction to V.P.