

TEST CERTIFICATE

Client: Redbank Operations Pty Ltd
Client Address: Level 1
143 Hay Street
Subiaco WA 6008
Project: Submitted Samples
Location: Redbank
Sample No: 09-MT-14603
Sample ID: SFDH09-004 (45.81 - 46.06)

Client Job No:
Order No:
Tested Date: 9/11/2009
SGS Job Number: 09-01-3096
Lab: Welshpool

UNIAXIAL COMPRESSIVE STRENGTH OF ROCK

AS4133.4.2.1

Failure Diagram approx to
scale

Sample Type: PQ3 Core


INITIAL SPECIMEN DETAILS

Core Diameter (mm): 82.9
Length/Diameter Ratio: 2.7

Bulk Dry Density (t/m3): 2.099

Moisture Content (%): 1.6

**UNIAXIAL
COMPRESSIVE
STRENGTH (MPa): 26.7**



Moisture Condition: Specimen tested at the
moisture condition as
received
Mode of Failure: Failed through Irregularities
Duration of Tests 6.8 mins

Note: Sample supplied by client.
Bulk Density value was determined by the Calliper method
Tested on a hydraulic compression machine

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

Client: Redbank Operations Pty Ltd
Client Address: Level 1
143 Hay Street
Subiaco WA 6008
Project: Submitted Samples
Location: Redbank
Sample No: 09-MT-14604
Sample ID: SFDH09-004 (237.33 - 237.56)

Client Job No:
Order No:
Tested Date: 9/11/2009
SGS Job Number: 09-01-3096
Lab: Welshpool

UNIAXIAL COMPRESSIVE STRENGTH OF ROCK

AS4133.4.2.1

Failure Diagram approx to
scale

Sample Type: PQ3 Core

INITIAL SPECIMEN DETAILS

Core Diameter (mm): 82.5
Length/Diameter Ratio: 2.6

Bulk Dry Density (t/m³): 2.114

Moisture Content (%): 1.4

**UNIAXIAL
COMPRESSIVE
STRENGTH (MPa): 29.0**



Moisture Condition: Specimen tested at the
moisture condition as
received

Mode of Failure: Shear Failure

Duration of Tests 6.1 mins

Note: Sample supplied by client.
Bulk Density value was determined by the Calliper method
Tested on a hydraulic compression machine

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

| | | | |
|-----------------|--|-----------------|------------|
| Client: | Redbank Operations Pty Ltd | Client Job No: | |
| Client Address: | Level 1 143 Hay Street Subiaco WA 6008 | Order No: | |
| Project: | Submitted Samples | Tested Date: | 9/11/2009 |
| Location: | Redbank | SGS Job Number: | 09-01-3096 |
| Sample No: | 09-MT-14605 | Lab: | Welshpool |
| Sample ID: | SFDH09-002 (60.08 - 60.30) | | |

UNIAXIAL COMPRESSIVE STRENGTH OF ROCK

AS4133.4.2.1

Failure Diagram approx to
scale

Sample Type: PQ3 Core

INITIAL SPECIMEN DETAILS

Core Diameter (mm): 82.5
 Length/Diameter Ratio: 2.6

Bulk Dry Density (t/m3): 2.533

Moisture Content (%): 0.3

**UNIAXIAL
 COMPRESSIVE
 STRENGTH (MPa): 124**



Moisture Condition: Specimen tested at the
moisture condition as
received

Mode of Failure: Shattered

Duration of Tests 6. mins

Note: Sample supplied by client.
 Bulk Density value was determined by the Calliper method
 Tested on a hydraulic compression machine

Approved Signatory:  (John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

| | | | |
|-----------------|--|-----------------|------------|
| Client: | Redbank Operations Pty Ltd | Client Job No: | |
| Client Address: | Level 1 143 Hay Street Subiaco WA 6008 | Order No: | |
| Project: | Submitted Samples | Tested Date: | 10/11/2009 |
| Location: | Redbank | SGS Job Number: | 09-01-3096 |
| Sample No: | 09-MT-14606 | Lab: | Welshpool |
| Sample ID: | BLDH09-002 (12.83 - 13.04) | | |

UNIAXIAL COMPRESSIVE STRENGTH OF ROCK

AS4133.4.2.1

Failure Diagram approx to
scale

Sample Type: PQ3 Core


INITIAL SPECIMEN DETAILS

Core Diameter (mm): 82.8
 Length/Diameter Ratio: 2.2

Bulk Dry Density (t/m3): 2.070

Moisture Content (%): 1.4

**UNIAXIAL
 COMPRESSIVE
 STRENGTH (MPa): 28.2**



Moisture Condition: Specimen tested at the
moisture condition as
received

Deviation from Standard: Less than required minimum
of 2.5

Mode of Failure: Shear Failure

Duration of Tests 5.4 mins

Note: Sample supplied by client.
 Bulk Density value was determined by the Calliper method
 Tested on a hydraulic compression machine

Approved Signatory: (John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

Client: Redbank Operations Pty Ltd
Client Address: Level 1
143 Hay Street
Subiaco WA 6008
Project: Submitted Samples
Location: Redbank
Sample No: 09-MT-14607
Sample ID: BLDH09-002 (119.30 - 119.55)

Client Job No:
Order No:
Tested Date: 9/11/2009
SGS Job Number: 09-01-3096
Lab: Welshpool

UNIAXIAL COMPRESSIVE STRENGTH OF ROCK

AS4133.4.2.1

Failure Diagram approx to
scale

Sample Type: PQ3 Core

INITIAL SPECIMEN DETAILS

Core Diameter (mm): 82.8
Length/Diameter Ratio: 2.7

Bulk Dry Density (t/m³): 2.282

Moisture Content (%): 0.5

**UNIAXIAL
COMPRESSIVE
STRENGTH (MPa): 52.6**



Moisture Condition: Specimen tested at the
moisture condition as
received

Mode of Failure: Shattered

Duration of Tests 11.3 mins

Note: Sample supplied by client.
Bulk Density value was determined by the Calliper method
Tested on a hydraulic compression machine

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

| | | | |
|-----------------|--|-----------------|------------|
| Client: | Redbank Operations Pty Ltd | Client Job No: | |
| Client Address: | Level 1 143 Hay Street Subiaco WA 6008 | Order No: | |
| Project: | Submitted Samples | Tested Date: | 10/11/2009 |
| Location: | Redbank | SGS Job Number: | 09-01-3096 |
| Sample No: | 09-MT-14609 | Lab: | Welshpool |
| Sample ID: | BLDH09-003 (55.82 - 56.06) | | |

UNIAXIAL COMPRESSIVE STRENGTH OF ROCK

AS4133.4.2.1

Failure Diagram approx to
scale

Sample Type: PQ3 Core

INITIAL SPECIMEN DETAILS

Core Diameter (mm): 82.1
 Length/Diameter Ratio: 2.8

Bulk Dry Density (t/m3): 2.452

Moisture Content (%): 0.4

**UNIAXIAL
 COMPRESSIVE
 STRENGTH (MPa): 81.0**



Moisture Condition: Specimen prepared at the
moisture condition as
received. Polished wet

Mode of Failure: Shear Failure

Duration of Tests 9.8 mins

Note: Sample supplied by client.
 Bulk Density value was determined by the Calliper method
 Tested on a hydraulic compression machine

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements



PO Box 219, Bentley, WA, 6982
 ph: 1300 781 744 fx: 9458 3700

COMPRESSIVE STRENGTH / MODULUS TEST REPORT CERTIFICATE

AS 4133 4.3 - 1993

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

LAB NO. : 09-MT-14610

LOCATION : Redbank

Client Job No.:

Sample No.: SFDH09-004

Date Tested : 10/11/09

Sample Id :

Test Type : Modulus Compression

Initial Specimen Details :

Sample Type :


Length/Diameter Ratio : 2.7

Rock Type : PQ3 Core

Bulk Dry Density (t/m³) : 2.021

Depth (m): (120.00 - 120.20)

Moisture Content (%) : 1.4 (AS 4133.1.1.1)



COMPRESSIVE STRENGTH / MODULUS DATA

U.C.S. (MPa) = 17.4 **Young's Modulus, E (GPa) =** 10.7

Mode of Failure : Axial Failure

- Note(s) :**
1. Young's Modulus determined from the straight line portion of the stress-strain plot.
 2. Strain measured using electrical resistance strain gauges.
 3. Sample supplied by client.
 4. Young's Modulus indicative values only, may require engineering interpretation

Approved Signatory : _____ (J. Reid)

Date 13/11/2009

Certificate No. : 09-MT-14610 / R301



Accreditation No. 2418

This document is issued in accordance with NATA's accreditation requirements

SN 2411

Client Address: Level 1 143 Hay Street Subiaco WA 6008

CLIENT : Redbank Operations Pty Ltd
JOB NO. : 09-01-3096
LAB NO. : 09-MT-14610



**Uniaxial compressive strength & Modulus
with Bulk Dry Density
notes on test AS 4133.4.3**

Sample Storage

4(c) Prior to testing the specimen was conditioned in a stable environment.

Specimen Preparation & conditioning

" 4 (a) Specimens were taken from selected pieces of core nominated by the Client. The depth range was adjusted, when required, to obtain the best possible specimen.

" 4 (c) Specimens were tested in the "As Received" condition –ie: removed from the protective wrapping, cut to length with a diamond saw, end polished (wet), measured, weighed and tested as quickly as practicable with the intention of retaining the existing moisture content

Test Equipment

" 3(a) &(h) The compression machine used was an "Avery" hydraulic compression machine, "A" Grade calibrated through its full range: Specimens were loaded at a constant rate of stress. Force was recorded through a pressure transducer & strain was captured through two opposing electronic strain gauges.

Deviations from the Standard Method

notes on test AS 4133.2.1.1

" 4 (a) Single specimens only were prepared.

" 4(b)(i)(ii)(iii)Dimensions & Mass for Bulk density calculation were determined on specimens immediately before loading. Dry Mass was calculated from the moisture content determination (AS 4133.1.1.1) taken from the UCS specimen.

" 4(b)(iv) Bulk density specimens were not immersed hence Porosity has not been calculated or reported. Bulk Dry Density has been reported. Full immersion would have affected the "As Received" condition.

Approved Signatory.....


(J. Reid)

Date: 13/11/2009

Certificate No. : 09-MT-14610 / R301



PO Box 219, Bentley, WA, 6982
ph: 1300 781 744 fx: 9458 3700

COMPRESSIVE STRENGTH / MODULUS TEST REPORT CERTIFICATE

AS 4133 4.3 - 1993

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

LAB NO. : 09-MT-14611

LOCATION : Redbank

Client Job No.:

Sample No.: SFDH09-002

Date Tested : 10/11/09

Sample Id :

Test Type : Modulus Compression

Initial Specimen Details :

Sample Type :

Length/Diameter Ratio : 2.3


Rock Type : PQ3 Core

Bulk Dry Density (t/m³) : 2.194

Depth (m): (228.79 - 229.02)

Moisture Content (%) : 1.0 (AS 4133.1.1.1)

Grain Size greater than 10 x Diam.



COMPRESSIVE STRENGTH / MODULUS DATA

U.C.S. (MPa) = 29.0

Young's Modulus, E (GPa) = 12.6

Mode of Failure : Shattered

Note(s) :

1. Young's Modulus determined from the straight line portion of the stress-strain plot.
2. Strain measured using electrical resistance strain gauges.
3. Sample supplied by client. Specimen tested in the as received condition. Polished wet
4. Young's Modulus indicative values only, may require engineering interpretation
5. Deviation from standard, length/diameter ratio does not conform with standard requirements

Approved Signatory :  (J. Reid)

Date 2/07/2009

Certificate No. : 09-MT-14611 / R301



Accreditation No. 2418

This document is issued in accordance with NATA's accreditation requirements

SN 2411

Client Address: Level 1 143 Hay Street Subiaco WA 6008

CLIENT : Redbank Operations Pty Ltd
 JOB NO. : 09-01-3096
 LAB NO. : 09-MT-14611



**Uniaxial compressive strength & Modulus
 with Bulk Dry Density
 notes on test AS 4133.4.3**

Sample Storage

4(c) Prior to testing the specimen was conditioned in a stable environment.

Specimen Preparation & conditioning

" 4 (a) Specimens were taken from selected pieces of core nominated by the Client. The depth range was adjusted, when required, to obtain the best possible specimen.

" 4 (c) Specimens were tested in the "As Received" condition –ie: removed from the protective wrapping, cut to length with a diamond saw, end polished, measured, weighed and tested as quickly as practicable with the intention of retaining the existing moisture content

Test Equipment

" 3(a) &(h) The compression machine used was an "Avery" hydraulic compression machine, "A" Grade calibrated through its full range: Specimens were loaded at a constant rate of stress. Force was recorded through a pressure transducer & strain was captured through two opposing electronic strain gauges.

Deviations from the Standard Method

" 4(a)(i) The Length to Diameter ratio may be less than 2.5, in some instances, due to the length of suitable sample available at the Client nominated depth

" 4(a)(i) The diameter of the specimen may not be greater than ten times the size of the largest grain of rock.

notes on test AS 4133.2.1.1

" 4 (a) Single specimens only were prepared.

" 4(b)(i)(ii)(iii) Dimensions & Mass for Bulk density calculation were determined on specimens immediately before loading. Dry Mass was calculated from the moisture content determination (AS 4133.1.1.1) taken from the UCS specimen.

" 4(b)(iv) Bulk density specimens were not immersed hence Porosity has not been calculated or reported. Bulk Dry Density has been reported. Full immersion would have affected the "As Received" condition.

Approved Signatory.....

(J. Reid)

Date: 2/07/2009

Certificate No. : 09-MT-14611 / R301



PO Box 219, Bentley, WA, 6982
ph: 1300 781 744 fx: 9458 3700

COMPRESSIVE STRENGTH / MODULUS TEST REPORT CERTIFICATE

AS 4133 4.3 - 1993

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

LAB NO. : 09-MT-14612

LOCATION : Redbank

Client Job No.:

Sample No.: BLDH09-002

Date Tested : 10/11/09

Sample Id :

Test Type : Modulus Compression

Initial Specimen Details :

Sample Type :


Length/Diameter Ratio : 2.4

Rock Type : PQ3 Core

Bulk Dry Density (t/m³) : 2.710

Depth (m): (230.28 - 230.51)

Moisture Content (%) : 0.2 (AS 4133.1.1.1)



COMPRESSIVE STRENGTH / MODULUS DATA

U.C.S. (MPa) = 121

Young's Modulus, E (GPa) = 41.7

Mode of Failure : Shattered

Note(s) :

1. Young's Modulus determined from the straight line portion of the stress-strain plot.
2. Strain measured using electrical resistance strain gauges.
3. Sample supplied by client. Specimen tested in the as received condition. Polished wet
4. Young's Modulus indicative values only, may require engineering interpretation
5. Deviation from standard, length/diameter ratio does not conform with standard requirements

Approved Signatory : _____ (J. Reid)

Date 2/07/2009

Certificate No. : 09-MT-14612 / R301



Accreditation No. 2418

This document is issued in accordance with NATA's accreditation requirements

SN 2411

Client Address: Level 1 143 Hay Street Subiaco WA 6008

CLIENT : Redbank Operations Pty Ltd
JOB NO. : 09-01-3096
LAB NO. : 09-MT-14612



**Uniaxial compressive strength & Modulus
with Bulk Dry Density
notes on test AS 4133.4.3**

Sample Storage

4(c) Prior to testing the specimen was conditioned in a stable environment.

Specimen Preparation & conditioning

" 4 (a) Specimens were taken from selected pieces of core nominated by the Client. The depth range was adjusted, when required, to obtain the best possible specimen.

" 4 (c) Specimens were tested in the "As Received" condition –ie: removed from the protective wrapping, cut to length with a diamond saw, end polished, measured, weighed and tested as quickly as practicable with the intention of retaining the existing moisture content

Test Equipment

" 3(a) &(h) The compression machine used was an "Avery" hydraulic compression machine, "A" Grade calibrated through its full range: Specimens were loaded at a constant rate of stress. Force was recorded through a pressure transducer & strain was captured through two opposing electronic strain gauges.

Deviations from the Standard Method


" 4(a)(i) The Length to Diameter ratio may be less than 2.5, in some instances, due to the length of suitable sample available at the Client nominated depth

notes on test AS 4133.2.1.1

" 4 (a) Single specimens only were prepared.

" 4(b)(i)(ii)(iii)Dimensions & Mass for Bulk density calculation were determined on specimens immediately before loading. Dry Mass was calculated from the moisture content determination (AS 4133.1.1.1) taken from the UCS specimen.

" 4(b)(iv) Bulk density specimens were not immersed hence Porosity has not been calculated or reported. Bulk Dry Density has been reported. Full immersion would have affected the "As Received" condition.

Approved Signatory..... 
(J. Reid)

Date: 2/07/2009

Certificate No. : 09-MT-14612 / R301



PO Box 219, Bentley, WA, 6982
 ph: 1300 781 744 fx: 9458 3700

COMPRESSIVE STRENGTH / MODULUS TEST REPORT CERTIFICATE

AS 4133 4.3 - 1993

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

LAB NO. : 09-MT-14613

LOCATION : Redbank

Client Job No.:

Sample No.: BLDH09-003

Date Tested : 10/11/09

Sample Id :

Test Type : Modulus Compression

Initial Specimen Details :

Sample Type :


Length/Diameter Ratio : 2.8

Rock Type : PQ3 Core

Bulk Dry Density (t/m³) : 2.274

Depth (m): (132.20 - 132.52)

Moisture Content (%) : 0.4 (AS 4133.1.1.1)



COMPRESSIVE STRENGTH / MODULUS DATA

U.C.S. (MPa) = 70.1 **Young's Modulus, E (GPa) =** 21.0

Mode of Failure : Shear Failure

- Note(s) :**
1. Young's Modulus determined from the straight line portion of the stress-strain plot.
 2. Strain measured using electrical resistance strain gauges.
 3. Sample supplied by client. Specimen tested in the as received condition. Polished wet
 4. Young's Modulus indicative values only, may require engineering interpretation

Approved Signatory : _____ (J. Reid)

Certificate No. : 09-MT-14613 / R301
Date 2/07/2009



Accreditation No. 2418

This document is issued in accordance with NATA's accreditation requirements

SN 2411

Client Address: Level 1 143 Hay Street Subiaco WA 6008

CLIENT : Redbank Operations Pty Ltd
JOB NO. : 09-01-3096
LAB NO. : 09-MT-14613



**Uniaxial compressive strength & Modulus
with Bulk Dry Density
notes on test AS 4133.4.3**

Sample Storage

4(c) Prior to testing the specimen was conditioned in a stable environment.

Specimen Preparation & conditioning

" 4 (a) Specimens were taken from selected pieces of core nominated by the Client. The depth range was adjusted, when required, to obtain the best possible specimen.

" 4 (c) Specimens were tested in the "As Received" condition –ie: removed from the protective wrapping, cut to length with a diamond saw, end polished, measured, weighed and tested as quickly as practicable with the intention of retaining the existing moisture content

Test Equipment

" 3(a) &(h) The compression machine used was an "Avery" hydraulic compression machine, "A" Grade calibrated through its full range: Specimens were loaded at a constant rate of stress. Force was recorded through a pressure transducer & strain was captured through two opposing electronic strain gauges.

Deviations from the Standard Method

" 4(a)(iii) The ends of the specimens have been polished to achieve flat ends to 0.02mm. In some instances, solution cavities are present at the specimen ends and the specimen may not meet this requirement.

notes on test AS 4133.2.1.1

" 4 (a) Single specimens only were prepared.

" 4(b)(i)(ii)(iii)Dimensions & Mass for Bulk density calculation were determined on specimens immediately before loading. Dry Mass was calculated from the moisture content determination (AS 4133.1.1.1) taken from the UCS specimen.

" 4(b)(iv) Bulk density specimens were not immersed hence Porosity has not been calculated or reported. Bulk Dry Density has been reported. Full immersion would have affected the "As Received" condition.

Approved Signatory.....



(J. Reid)

Date: 2/07/2009

Certificate No. : 09-MT-14613 / R301

TEST CERTIFICATE

| | | | |
|-----------------|--|-----------------|------------|
| Client: | Redbank Operations Pty Ltd | Client Job No: | |
| Client Address: | Level 1 143 Hay Street Subiaco WA 6008 | Order No: | |
| Project: | Submitted Samples | Tested Date: | 10/11/2009 |
| Location: | Redbank | SGS Job Number: | 09-01-3096 |
| Sample No: | 09-MT-14614 | Lab: | Welshpool |
| Sample ID: | SFDH09-004 (45.56 - 45.67) | | |

INDIRECT TENSILE STRENGTH

ISRM Doc 8 Pt 2 (Brazil Method)

Initial Specimen Details

| | |
|---------------------------------------|-------|
| Height / Diameter Ratio: | 0.5 |
| Bulk Dry Density (t/m ³): | 2.134 |
| Water Content (%): | 0.6 |
| Specimen Height (mm): | 43 |
| Specimen Diameter (mm): | 83 |

**INDIRECT
TENSILE STRENGTH 9.68
(MPa):**

Note: Sample supplied by client.

Bulk Density Value was determined by the Calliper Method

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

| | | | |
|-----------------|--|-----------------|------------|
| Client: | Redbank Operations Pty Ltd | Client Job No: | |
| Client Address: | Level 1 143 Hay Street Subiaco WA 6008 | Order No: | |
| Project: | Submitted Samples | Tested Date: | 11/11/2009 |
| Location: | Redbank | SGS Job Number: | 09-01-3096 |
| Sample No: | 09-MT-14615 | Lab: | Welshpool |
| Sample ID: | SFDH09-004 (237.94 - 238.04) | | |

INDIRECT TENSILE STRENGTH

ISRM Doc 8 Pt 2 (Brazil Method)

Initial Specimen Details

| | |
|--------------------------|-------|
| Height / Diameter Ratio: | 0.5 |
| Bulk Dry Density (t/m3) | 2.152 |
| Water Content (%): | 0.7 |
| Specimen Height (mm): | 43 |
| Specimen Diameter (mm): | 82 |

**INDIRECT
TENSILE STRENGTH 5.79
(MPa):**

Note: Sample supplied by client.

Bulk Density Value was determined by the Calliper Method

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

Client: Redbank Operations Pty Ltd
Client Address: Level 1
143 Hay Street
Subiaco WA 6008
Project: Submitted Samples
Location: Redbank
Sample No: 09-MT-14616
Sample ID: SFDH09-002 (59.95 - 60.08)

Client Job No:
Order No:
Tested Date: 10/11/2009
SGS Job Number: 09-01-3096
Lab: Welshpool

INDIRECT TENSILE STRENGTH

ISRM Doc 8 Pt 2 (Brazil Method)

Initial Specimen Details

| | |
|---------------------------------------|-------|
| Height / Diameter Ratio: | 0.5 |
| Bulk Dry Density (t/m ³): | 2.485 |
| Water Content (%): | 0.2 |
| Specimen Height (mm): | 42 |
| Specimen Diameter (mm): | 82 |

**INDIRECT
TENSILE STRENGTH** **13.6**
(MPa):

Note: Sample supplied by client.

Bulk Density Value was determined by the Calliper Method

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

Client: Redbank Operations Pty Ltd
Client Address: Level 1
143 Hay Street
Subiaco WA 6008
Project: Submitted Samples
Location: Redbank
Sample No: 09-MT-14617
Sample ID: SFDH09-002 (229.02 - 229.27)

Client Job No:
Order No:
Tested Date: 10/11/2009
SGS Job Number: 09-01-3096
Lab: Welshpool

INDIRECT TENSILE STRENGTH

ISRM Doc 8 Pt 2 (Brazil Method)

Initial Specimen Details

| | |
|---------------------------------------|-------|
| Height / Diameter Ratio: | 0.5 |
| Bulk Dry Density (t/m ³): | 2.210 |
| Water Content (%): | 0.8 |
| Specimen Height (mm): | 43 |
| Specimen Diameter (mm): | 82 |

**INDIRECT
TENSILE STRENGTH 3.69
(MPa):**

Note: Sample supplied by client.

Bulk Density Value was determined by the Calliper Method

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

| | | | |
|-----------------|--|-----------------|------------|
| Client: | Redbank Operations Pty Ltd | Client Job No: | |
| Client Address: | Level 1 143 Hay Street Subiaco WA 6008 | Order No: | |
| Project: | Submitted Samples | Tested Date: | 10/11/2009 |
| Location: | Redbank | SGS Job Number: | 09-01-3096 |
| Sample No: | 09-MT-14618 | Lab: | Welshpool |
| Sample ID: | BLDH09-002 (119.55 - 119.66) | | |

INDIRECT TENSILE STRENGTH

ISRM Doc 8 Pt 2 (Brazil Method)

Initial Specimen Details

| | |
|---------------------------------------|-------|
| Height / Diameter Ratio: | 0.5 |
| Bulk Dry Density (t/m ³): | 2.272 |
| Water Content (%): | 0.4 |
| Specimen Height (mm): | 43 |
| Specimen Diameter (mm): | 83 |

INDIRECT

| | |
|--|-------------|
| TENSILE STRENGTH (MPa): | 4.48 |
|--|-------------|

Note: Sample supplied by client.

Bulk Density Value was determined by the Calliper Method

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

| | | | |
|-----------------|--|-----------------|------------|
| Client: | Redbank Operations Pty Ltd | Client Job No: | |
| Client Address: | Level 1 143 Hay Street Subiaco WA 6008 | Order No: | |
| Project: | Submitted Samples | Tested Date: | 10/11/2009 |
| Location: | Redbank | SGS Job Number: | 09-01-3096 |
| Sample No: | 09-MT-14619 | Lab: | Welshpool |
| Sample ID: | BLDH09-002 (227.33 - 227.46) | | |

INDIRECT TENSILE STRENGTH

ISRM Doc 8 Pt 2 (Brazil Method)

Initial Specimen Details

| | |
|---------------------------------------|-------|
| Height / Diameter Ratio: | 0.5 |
| Bulk Dry Density (t/m ³): | 2.700 |
| Water Content (%): | 0.3 |
| Specimen Height (mm): | 43 |
| Specimen Diameter (mm): | 83 |

**INDIRECT
TENSILE STRENGTH** **6.19**
(MPa):

Note: Sample supplied by client.

Bulk Density Value was determined by the Calliper Method

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

| | | | |
|-----------------|--|-----------------|------------|
| Client: | Redbank Operations Pty Ltd | Client Job No: | |
| Client Address: | Level 1 143 Hay Street Subiaco WA 6008 | Order No: | |
| Project: | Submitted Samples | Tested Date: | 10/11/2009 |
| Location: | Redbank | SGS Job Number: | 09-01-3096 |
| Sample No: | 09-MT-14620 | Lab: | Welshpool |
| Sample ID: | BLDH09-002 (205.66 - 205.78) | | |

INDIRECT TENSILE STRENGTH

ISRM Doc 8 Pt 2 (Brazil Method)

Initial Specimen Details

| | |
|--------------------------|-------|
| Height / Diameter Ratio: | 0.5 |
| Bulk Dry Density (t/m3) | 2.626 |
| Water Content (%): | 0.5 |
| Specimen Height (mm): | 42 |
| Specimen Diameter (mm): | 83 |

**INDIRECT
TENSILE STRENGTH 5.67
(MPa):**

Note: Sample supplied by client.

Bulk Density Value was determined by the Calliper Method

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

Client: Redbank Operations Pty Ltd
Client Address: Level 1
143 Hay Street
Subiaco WA 6008
Project: Submitted Samples
Location: Redbank
Sample No: 09-MT-14621
Sample ID: BLDH09-003 (132.52 - 132.71)

Client Job No:
Order No:
Tested Date: 10/11/2009
SGS Job Number: 09-01-3096
Lab: Welshpool

INDIRECT TENSILE STRENGTH

ISRM Doc 8 Pt 2 (Brazil Method)

Initial Specimen Details

| | |
|---------------------------------------|-------|
| Height / Diameter Ratio: | 0.5 |
| Bulk Dry Density (t/m ³): | 2.282 |
| Water Content (%): | 0.3 |
| Specimen Height (mm): | 43 |
| Specimen Diameter (mm): | 82 |

**INDIRECT
TENSILE STRENGTH** **6.09**
(MPa):

Note: Sample supplied by client.

Bulk Density Value was determined by the Calliper Method

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

Client: Redbank Operations Pty Ltd
Client Address: Level 1
143 Hay Street
Subiaco WA 6008
Project: Submitted Samples
Location: Redbank
Sample No: 09-MT-14622
Sample ID: SFDH09-004 (237.82 - 237.94)

Client Job No:
Order No:
Tested Date: 11/11/2009
SGS Job Number: 09-01-3096
Lab: Welshpool

SLAKE DURABILITY

AS4133.3.4

| Slaking Fluid | Tap Water |
|-----------------------------------|------------------------------|
| Temperature of Fluid - degrees C | 24 |
| First Cycle | |
| SLAKE DURABILITY INDEX (%) | 99.9 |
| Appearance Particles Retained | No change |
| Appearance Particles Passing | Slightly cloudy |
| Second Cycle | |
| SLAKE DURABILITY INDEX (%) | 99.4 |
| Appearance Particles Retained | slight rounding of particles |
| Appearance Particles Passing | cloudy |

Note: Sample supplied by client.

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

Client: Redbank Operations Pty Ltd
Client Address: Level 1
143 Hay Street
Subiaco WA 6008
Project: Submitted Samples
Location: Redbank
Sample No: 09-MT-14623
Sample ID: SFDH09-002 (86.70 - 86.86)

Client Job No:
Order No:
Tested Date: 11/11/2009
SGS Job Number: 09-01-3096
Lab: Welshpool

SLAKE DURABILITY

AS4133.3.4

| Slaking Fluid | Tap Water |
|-----------------------------------|-----------------|
| Temperature of Fluid - degrees C | 24 |
| First Cycle | |
| SLAKE DURABILITY INDEX (%) | 100.0 |
| Appearance Particles Retained | No Change |
| Appearance Particles Passing | Slightly cloudy |
| Second Cycle | |
| SLAKE DURABILITY INDEX (%) | 99.7 |
| Appearance Particles Retained | No change |
| Appearance Particles Passing | slightly cloudy |

Note: Sample supplied by client.

Approved Signatory:

(John.Reid)

Date: 13/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

Client: Redbank Operations Pty Ltd
Client Address: Level 1
143 Hay Street
Subiaco WA 6008
Project: Submitted Samples
Location: Redbank
Sample No: 09-MT-14624
Sample ID: BLDH09-002 (70.50 - 70.65)

Client Job No:
Order No:
Tested Date: 13/11/2009
SGS Job Number: 09-01-3096
Lab: Welshpool

SLAKE DURABILITY

AS4133.3.4

| Slaking Fluid | Tap Water |
|-----------------------------------|----------------------------------|
| Temperature of Fluid - degrees C | 24 |
| First Cycle | |
| SLAKE DURABILITY INDEX (%) | 99.4 |
| Appearance Particles Retained | Slight rounding - few broke |
| Appearance Particles Passing | cloudy |
| Second Cycle | |
| SLAKE DURABILITY INDEX (%) | 98.8 |
| Appearance Particles Retained | Slight rounding - few more broke |
| Appearance Particles Passing | cloudy |

Note: Sample supplied by client.

Approved Signatory:

(John.Reid)

Date: 18/11/2009



This document is issued in accordance with NATA's accreditation requirements

TEST CERTIFICATE

Client: Redbank Operations Pty Ltd
Client Address: Level 1
143 Hay Street
Subiaco WA 6008
Project: Submitted Samples
Location: Redbank
Sample No: 09-MT-14625
Sample ID: BLDH09-002 (227.46 - 227.61)

Client Job No:
Order No:
Tested Date: 13/11/2009
SGS Job Number: 09-01-3096
Lab: Welshpool

SLAKE DURABILITY

AS4133.3.4

| Slaking Fluid | Tap Water |
|-----------------------------------|----------------------|
| Temperature of Fluid - degrees C | 24 |
| First Cycle | |
| SLAKE DURABILITY INDEX (%) | 99.7 |
| Appearance Particles Retained | Very slight rounding |
| Appearance Particles Passing | cloudy |
| Second Cycle | |
| SLAKE DURABILITY INDEX (%) | 99.2 |
| Appearance Particles Retained | Slight rounding |
| Appearance Particles Passing | cloudy |

Note: Sample supplied by client.

Approved Signatory:

(John.Reid)

Date: 18/11/2009



This document is issued in accordance with NATA's accreditation requirements




DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14626 RDS Attachment 1 of 5

CLIENT : Redbank Operations Pty Ltd
PROJECT : Submitted Samples
LOCATION : Redbank
Sample Id : , Sample No. : , Depth : (193.00 - 193.20)
Test Type : Direct Shear , Multi-Stage on Existing Discontinuity
Initial Specimen Details :
 Core Diameter : 82.1 mm
 Shear Plane Dip Angle : 52°

JOB NO. : 09-01-3096
Lab No. : 09-MT-14626
Date Tested : 18-Nov-09
Discontinuity Type : Existing joint



SHEAR STAGE DATA

| Stage No | Strain Rate (mm/min) | Δ_{sf} (mm) | ϵ_{sf} (%) | Normal Stress | | Shear Stress |
|----------|----------------------|--------------------|---------------------|---------------------|---------------------|----------------|
| | | | | σ_{no} (kPa) | σ_{nf} (kPa) | τ_f (kPa) |
| 1 | 0.625 | 4.57 | 4.4 | 200 | 212 | 262 |
| 2 | 0.625 | 5.93 | 5.7 | 400 | 431 | 448 |
| 3 | 0.625 | 7.73 | 7.4 | 800 | 884 | 719 |

Peak - Cohesion, C (kPa) : 136

Friction Angle, ϕ (degrees) : 34

Shear Plane description : Pre-test : Rough, Undulating..
 Post-test : As above with significant grinding and slight crumbling.

Notes : Shear plane dip angle in relation to core axis only.
 Line of best fit has been used to determine cohesion & friction angle values.
 Sample supplied by client.

Sample tested in "as received" condition.

Certificate No. : 09-MT-14626 RDS

Authorised Signatory : _____ (L. Harris)

Date: 18/11/2009

36 Railway Parade Welshpool WA 6106 Phone 1300 781 744 Fax (08) 9458 3700

DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14626 RDS Attachment 2 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14626

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (193.00 - 193.20)

Discontinuity Type : Existing joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :

Core Diameter : 82.1 mm

Shear Plane Dip Angle : 52°

SHEAR STRESS Vs SHEAR DISPLACEMENT



Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009

DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14626 R DS Attachment 3 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14626

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (193.00 - 193.20)

Discontinuity Type : Existing joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :

Core Diameter : 82.1 mm

Shear Plane Dip Angle : 52°

SHEAR STRESS Vs NORMAL STRESS



Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009

SPECIMEN DESCRIPTION

REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14626 RDS Attachment 5 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14626

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (193.00 - 193.20)

Discontinuity Type : Existing joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :


Core Diameter : 82.1 mm

Shear Plane Dip Angle : 52°

SPECIMEN PROFILE OF LOWER HALF



SHEAR SURFACE AREA OF LOWER HALF



Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009
PT-AU-IND(MTE)-TE-R400.CEP/A/01.01.2009

DIRECT SHEAR TEST

REPORT CERTIFICATE


(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14626 RDS Attachment 4 of 5

CLIENT : Redbank Operations Pty Ltd
PROJECT : Submitted Samples
LOCATION : Redbank
Sample Id : , Sample No. : , Depth : (193.00 - 193.20)
Test Type : Direct Shear , Multi-Stage on Existing Discontinuity
Initial Specimen Details :
Core Diameter : 82.1 mm
Shear Plane Dip Angle : 52°

JOB NO. : 09-01-3096
Lab No. : 09-MT-14626
Date Tested : 18-Nov-09
Discontinuity Type : Existing joint

NORMAL DISPLACEMENT Vs SHEAR DISPLACEMENT



Authorised Signatory : _____ *L. Harris* _____

(L. Harris)

Date: 18/11/2009




DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14627 RDS Attachment 1 of 5

CLIENT : Redbank Operations Pty Ltd
PROJECT : Submitted Samples
LOCATION : Redbank
Sample Id : , Sample No. : , Depth : (101.90 - 102.23)
Test Type : Direct Shear , Multi-Stage on Existing Discontinuity
Initial Specimen Details :
 Core Diameter : 82.9 mm
 Shear Plane Dip Angle : 38°

JOB NO. : 09-01-3096
Lab No. : 09-MT-14627
Date Tested : 18-Nov-09
Discontinuity Type : Existing joint



SHEAR STAGE DATA

| Stage No | Strain Rate (mm/min) | Δ_{sf} (mm) | ϵ_{sf} (%) | Normal Stress | | Shear Stress |
|----------|----------------------|--------------------|---------------------|---------------------|---------------------|----------------|
| | | | | σ_{no} (kPa) | σ_{nf} (kPa) | τ_f (kPa) |
| 1 | 0.625 | 2.66 | 2.0 | 200 | 205 | 139 |
| 2 | 0.625 | 4.39 | 3.3 | 406 | 424 | 309 |
| 3 | 0.625 | 4.59 | 3.4 | 800 | 836 | 543 |

Peak - Cohesion, C (kPa) : 23 **Friction Angle, ϕ (degrees) :** 32

Shear Plane description : Pre-test : Rough, Planar.
 Post-test : As above with significant grinding..

Notes : Shear plane dip angle in relation to core axis only.
 Line of best fit has been used to determine cohesion & friction angle values.
 Sample supplied by client.

Sample tested in "as received" condition.

Certificate No. : 09-MT-14627 RDS

Authorised Signatory : _____ (L. Harris)

Date: 18/11/2009

36 Railway Parade Welshpool WA 6106 Phone 1300 781 744 Fax (08) 9458 3700

DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14627 RDS Attachment 2 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14627

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (101.90 - 102.23)

Discontinuity Type : Existing joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :

Core Diameter : 82.9 mm

Shear Plane Dip Angle : 38°

SHEAR STRESS Vs SHEAR DISPLACEMENT



Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009

DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14627 R DS Attachment 3 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14627

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (101.90 - 102.23)

Discontinuity Type : Existing joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :

Core Diameter : 82.9 mm

Shear Plane Dip Angle : 38°

SHEAR STRESS Vs NORMAL STRESS



Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009

SPECIMEN DESCRIPTION

REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14627 RDS Attachment 5 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14627

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (101.90 - 102.23)

Discontinuity Type : Existing joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :


Core Diameter : 82.9 mm

Shear Plane Dip Angle : 38°

SPECIMEN PROFILE OF LOWER HALF



SHEAR SURFACE AREA OF LOWER HALF



>>>> DIRECTION OF SHEAR >>>>

Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009
PT-AU-IND(MTE)-TE-R400.CEP/A/01.01.2009

DIRECT SHEAR TEST

REPORT CERTIFICATE


(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14627 RDS Attachment 4 of 5

CLIENT : Redbank Operations Pty Ltd
PROJECT : Submitted Samples
LOCATION : Redbank
Sample Id : , Sample No. : , Depth : (101.90 - 102.23)
Test Type : Direct Shear , Multi-Stage on Existing Discontinuity
Initial Specimen Details :
 Core Diameter : 82.9 mm
 Shear Plane Dip Angle : 38°

JOB NO. : 09-01-3096
Lab No. : 09-MT-14627
Date Tested : 18-Nov-09
Discontinuity Type : Existing joint

NORMAL DISPLACEMENT Vs SHEAR DISPLACEMENT



Authorised Signatory : _____ *L. Harris* _____

(L. Harris)

Date: 18/11/2009




DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14628 RDS Attachment 1 of 5

CLIENT : Redbank Operations Pty Ltd
PROJECT : Submitted Samples
LOCATION : Redbank
Sample Id : , Sample No. : , Depth : (228.33 - 228.50)
Test Type : Direct Shear , Multi-Stage on Existing Discontinuity
Initial Specimen Details :
 Core Diameter : 82.8 mm
 Shear Plane Dip Angle : 67°

JOB NO. : 09-01-3096
Lab No. : 09-MT-14628
Date Tested : 18-Nov-09
Discontinuity Type : Existing Joint



SHEAR STAGE DATA

| Stage No | Strain Rate (mm/min) | Δ_{sf} (mm) | ϵ_{sf} (%) | Normal Stress | | Shear Stress |
|----------|----------------------|--------------------|---------------------|---------------------|---------------------|----------------|
| | | | | σ_{no} (kPa) | σ_{nf} (kPa) | τ_f (kPa) |
| 1 | 0.625 | 3.17 | 3.5 | 200 | 209 | 156 |
| 2 | 0.625 | 3.66 | 4.1 | 400 | 422 | 285 |
| 3 | 0.625 | 4.53 | 5.0 | 800 | 855 | 540 |

Peak - Cohesion, C (kPa) : 33 **Friction Angle, ϕ (degrees) :** 31

Shear Plane description : Pre-test : Smooth, Planar.
 Post-test : As above with slight grinding..

Notes : Shear plane dip angle in relation to core axis only.
 Line of best fit has been used to determine cohesion & friction angle values.
 Sample supplied by client.

Sample tested in "as received" condition.

Certificate No. : 09-MT-14628 RDS

Authorised Signatory : _____ (L. Harris) **Date:** 18/11/2009

36 Railway Parade Welshpool WA 6106 Phone 1300 781 744 Fax (08) 9458 3700

DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14628 RDS Attachment 2 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14628

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (228.33 - 228.50)

Discontinuity Type : Existing Joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :

Core Diameter : 82.8 mm

Shear Plane Dip Angle : 67°

SHEAR STRESS Vs SHEAR DISPLACEMENT



Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009

DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14628 R DS Attachment 3 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14628

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (228.33 - 228.50)

Discontinuity Type : Existing Joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :

Core Diameter : 82.8 mm

Shear Plane Dip Angle : 67°

SHEAR STRESS Vs NORMAL STRESS



Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009

SPECIMEN DESCRIPTION

REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14628 RDS Attachment 5 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14628

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (228.33 - 228.50)

Discontinuity Type : Existing Joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :


Core Diameter : 82.8 mm

Shear Plane Dip Angle : 67°

SPECIMEN PROFILE OF LOWER HALF



SHEAR SURFACE AREA OF LOWER HALF



>>>> DIRECTION OF SHEAR >>>>

Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009
44 (AU)-[IND(MTE)]-TE-R400.CEP/A/01.01.2009

DIRECT SHEAR TEST

REPORT CERTIFICATE


(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14628 RDS Attachment 4 of 5

CLIENT : Redbank Operations Pty Ltd
PROJECT : Submitted Samples
LOCATION : Redbank
Sample Id : , Sample No. : , Depth : (228.33 - 228.50)
Test Type : Direct Shear , Multi-Stage on Existing Discontinuity
Initial Specimen Details :
 Core Diameter : 82.8 mm
 Shear Plane Dip Angle : 67°

JOB NO. : 09-01-3096
Lab No. : 09-MT-14628
Date Tested : 18-Nov-09
Discontinuity Type : Existing Joint

NORMAL DISPLACEMENT Vs SHEAR DISPLACEMENT



Authorised Signatory : _____ *L. Harris* _____

(L. Harris)

Date: 18/11/2009




DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14629 RDS Attachment 1 of 5

CLIENT : Redbank Operations Pty Ltd
PROJECT : Submitted Samples
LOCATION : Redbank
Sample Id : , Sample No. : , Depth : (149.76 - 150.18)
Test Type : Direct Shear , Multi-Stage on Existing Discontinuity
Initial Specimen Details :
 Core Diameter : 82.1 mm
 Shear Plane Dip Angle : 50°

JOB NO. : 09-01-3096
Lab No. : 09-MT-14629
Date Tested : 18-Nov-09
Discontinuity Type : Existing Joint



SHEAR STAGE DATA

| Stage No | Strain Rate (mm/min) | Δ_{sf} (mm) | ϵ_{sf} (%) | Normal Stress | | Shear Stress |
|----------|----------------------|--------------------|---------------------|---------------------|---------------------|----------------|
| | | | | σ_{no} (kPa) | σ_{nf} (kPa) | τ_f (kPa) |
| 1 | 0.625 | 3.50 | 3.6 | 200 | 210 | 229 |
| 2 | 0.625 | 4.24 | 4.4 | 400 | 424 | 396 |
| 3 | 0.625 | 5.72 | 5.9 | 800 | 866 | 661 |

Peak - Cohesion, C (kPa) : 104

Friction Angle, ϕ (degrees) : 33

Shear Plane description : Pre-test : Smooth, Stepped.

Post-test : As above with significant grinding and fracturing..

Notes : Shear plane dip angle in relation to core axis only.
 Line of best fit has been used to determine cohesion & friction angle values.
 Sample supplied by client.

Sample tested in "as received" condition.

Certificate No. : 09-MT-14629 RDS

Authorised Signatory : _____ (L. Harris)

Date: 18/11/2009

36 Railway Parade Welshpool WA 6106 Phone 1300 781 744 Fax (08) 9458 3700

DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14629 RDS Attachment 2 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14629

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (149.76 - 150.18)

Discontinuity Type : Existing Joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :

Core Diameter : 82.1 mm

Shear Plane Dip Angle : 50°

SHEAR STRESS Vs SHEAR DISPLACEMENT



Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009

DIRECT SHEAR TEST REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14629 R DS Attachment 3 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14629

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (149.76 - 150.18)

Discontinuity Type : Existing Joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :

Core Diameter : 82.1 mm

Shear Plane Dip Angle : 50°

SHEAR STRESS Vs NORMAL STRESS



Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009

SPECIMEN DESCRIPTION

REPORT CERTIFICATE

(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14629 RDS Attachment 5 of 5

CLIENT : Redbank Operations Pty Ltd

JOB NO. : 09-01-3096

PROJECT : Submitted Samples

Lab No. : 09-MT-14629

LOCATION : Redbank

Date Tested : 18-Nov-09

Sample Id : , Sample No. : , Depth : (149.76 - 150.18)

Discontinuity Type : Existing Joint


Test Type : Direct Shear , Multi-Stage on Existing Discontinuity

Initial Specimen Details :


Core Diameter : 82.1 mm

Shear Plane Dip Angle : 50°

SPECIMEN PROFILE OF LOWER HALF



SHEAR SURFACE AREA OF LOWER HALF



Authorised Signatory : _____ *L. Harris* _____ (L. Harris)

Date: 18/11/2009
PT-AU-[IND(MTE)]-TE-R400.CEP/A/01.01.2009

DIRECT SHEAR TEST

REPORT CERTIFICATE


(Reference Method : ISRM - Doc. 1 (Field), Part 2)

09-MT-14629 RDS Attachment 4 of 5

CLIENT : Redbank Operations Pty Ltd
PROJECT : Submitted Samples
LOCATION : Redbank
Sample Id : , Sample No. : , Depth : (149.76 - 150.18)
Test Type : Direct Shear , Multi-Stage on Existing Discontinuity
Initial Specimen Details :
 Core Diameter : 82.1 mm
 Shear Plane Dip Angle : 50°

JOB NO. : 09-01-3096
Lab No. : 09-MT-14629
Date Tested : 18-Nov-09
Discontinuity Type : Existing Joint

NORMAL DISPLACEMENT Vs SHEAR DISPLACEMENT



Authorised Signatory : _____ *L. Harris* _____

(L. Harris)

Date: 18/11/2009



NOTES ON TESTING

| Job No. | Lab Sample No: | Client Sample ID: | Observations / Comments / Reason Unable to Test |
|----------------|-----------------------|--------------------------------|--|
| 09-01-3096 | 09-MT-14608 | BLDH09-002 (205.46-205.66m) | Sample fractured during preparation. Insufficient suitable sample remaining for UCS testing. |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |
| | | | |

This form is used to record reasons as to why changes or deviations in testing occur or as to why a test could not be performed. Must be kept with head sheet.